

**Parsons, Duane**

**To:** Tower, Steven; Kruchek, David  
**Cc:** Marschall, JR  
**Subject:** Revision 1 of the Security Cluster RLCR

The attached report is Revision 1 of the Security Cluster Reconnaissance Characterization Report (RLCR). Per Dave Kruchek's comments on Revision 0 of the Security Cluster RLCR, we have made the following changes:

Section 4.1.2 – added additional justification for the Beryllium sampling design.  
Attachment G – added additional detail on the Data Quality Assessment  
Attachment H – added the Historical Site Assessment Reports

If you have any additional comments please contact me at x6458. Thank You


*Duane Parsons*

RISS Facility Characterization Coordinator

Phone: 303-966-6458

Pager: 303-212-3734

Fax: 303-966-6678



1/101

DOCUMENT CLASSIFICATION  
REVIEW WAIVER PER  
CLASSIFICATION OFFICE

ADMIN RECORD

IA-A-000818



# **Rocky Flats Environmental Technology Site**

## **RECONNAISSANCE LEVEL CHARACTERIZATION REPORT (RLCR)**

### **SECURITY CLUSTER CLOSURE PROJECT** (Buildings 550, 761, 901, 762, 762A, 792, 792A)

**REVISION 1**


**May 17, 2001**

## RECONNAISSANCE LEVEL CHARACTERIZATION REPORT (RLCR)

### SECURITY CLUSTER CLOSURE PROJECT REVISION 1

May 15, 2001

Reviewed by:

  
Steve Luker, Quality Assurance

Date: 5/17/01

Reviewed by:

  
Michael Chritton, RISS ESH&Q Manager

Date: 5/18/01

Approved by:

  
JR Marschall, K-H Project Manager

Date: 5/21/01

ABBREVIATIONS/ACRONYMS.....		IV
1	INTRODUCTION.....	6
1.1	PURPOSE.....	6
1.2	SCOPE.....	6
1.3	DATA QUALITY OBJECTIVES .....	6
2	HISTORICAL SITE ASSESSMENT .....	7
3	RADIOLOGICAL CHARACTERIZATION AND HAZARDS.....	7
3.1	RADIOLOGICAL CHARACTERIZATION .....	7
3.2	RADIOLOGICAL HAZARDS SUMMARY.....	7
4	CHEMICAL CHARACTERIZATION AND HAZARDS .....	8
4.1	CHEMICAL CHARACTERIZATION.....	8
4.1.1	Asbestos .....	8
4.1.2	Beryllium (Be).....	8
4.1.3	RCRA/CERCLA Constituents [including metals and volatile and semi-volatile organic compounds (VOCs & SVOCs)].....	9
4.1.4	Polychlorinated Biphenyls (PCBs) .....	9
4.2	CHEMICAL HAZARDS SUMMARY .....	10
4.2.1	Asbestos .....	10
4.2.2	Beryllium.....	10
4.2.3	RCRA/CERCLA Constituents.....	10
4.2.4	PCBs .....	10
5	PHYSICAL HAZARDS.....	10
6	DATA QUALITY ASSESSMENT .....	11
7	DECOMMISSIONING WASTE TYPES AND VOLUME ESTIMATES.....	11
8	FACILITY CLASSIFICATION AND CONCLUSIONS .....	12
9	REFERENCES.....	13

A	Facility Location Map
B	Radiological Characterization Package
C	Chemical Characterization Package
D	Radiological Data Summaries and Survey Maps
E	Chemical Data Summaries and Sample Maps
F	Decommissioning Waste Types And Volume Estimates
G	Data Quality Assessment (DQA) Detail
H	Historical Site Assessment Reports

## ABBREVIATIONS/ACRONYMS

ACM	Asbestos containing material
Be	Beryllium
CDPHE	Colorado Department of Public Health and the Environment
DCGL <sub>EMC</sub>	Derived Concentration Guideline Level – elevated measurement comparison
DCGL <sub>w</sub>	Derived Concentration Guideline Level – Wilcoxon Rank Sum Test
D&D	Decontamination and Decommissioning
DDCP	Decontamination and Decommissioning Characterization Protocol
DOE	U.S. Department of Energy
DPP	Decommissioning Program Plan
DQA	Data quality assessment
DQOs	Data quality objectives
EPA	U.S. Environmental Protection Agency
FDPM	Facility Disposition Program Manual
HVAC	Heating, ventilation, air conditioning
HSAR	Historical Site Assessment Report
IHSS	Individual Hazardous Substance Site
IWCP	Integrated Work Control Package
K-H	Kaiser-Hill
LBP	Lead-based paint
LLW	Low-level waste
MARSSIM	Multi-Agency Radiation Survey and Site Investigation Manual
MDA	Minimum detectable activity
MDC	Minimum detectable concentration
NORM	Naturally occurring radioactive material
NRA	Non-Rad-Added Verification
OSHA	Occupational Safety and Health Administration
PARCC	Precision, accuracy, representativeness, comparability and completeness
PCBs	Polychlorinated Biphenyls
PDS	Pre-demolition survey
QC	Quality Control
RCRA	Resource Conservation and Recovery Act
RFCA	Rocky Flats Cleanup Agreement
RFETS	Rocky Flats Environmental Technology Site
RFFO	Rocky Flats Field Office
RLC	Reconnaissance Level Characterization
RLCR	Reconnaissance Level Characterization Report
RSP	Radiological Safety Practices
SVOCs	Semi-volatile organic compounds
TSA	Total surface activity
VOCs	Volatile organic compounds

## EXECUTIVE SUMMARY

A Reconnaissance Level Characterization (RLC) was performed to enable facility "Typing" per the DPP (10/8/98) and compliant disposition and waste management of facilities 550, 761, 901, 762, 762A, 792, and 792A (a.k.a. Security Cluster). Because these facilities were anticipated to be Type 1 facilities, the characterization was performed in accordance with the Pre-Demolition Survey Plan (MAN-127-PDSP). All facilities surfaces were characterized in this RLC, including the interior and exterior surfaces of the facilities (i.e., floors (slabs), walls, ceilings and roofs). Environmental media beneath and surrounding the facilities were not within the scope of this RLC Report (RLCR) and will be addressed using the Soil Disturbance Permit process.

The RLC encompassed both radiological and chemical characterization to enable compliant disposition and waste management pursuant to the D&D Characterization Protocol (MAN-077-DDCP). The characterization built upon physical, chemical and radiological hazards identified in the facility specific Historical Site Assessment Reports.

Results indicate that no radiological contamination exists in excess of the prescribed release limits of DOE Order 5400.5. The roof flashing materials of Buildings 762 and 792 contain asbestos, in both friable and non-friable form. Fluorescent light ballasts that may contain PCBs. PCB ballasts and asbestos containing materials will be removed and disposed of in compliance with Environmental Protection Agency (EPA) and Colorado Department of Public Health and Environment (CDPHE) regulations. Painted facility surfaces may contain PCBs. All demolition debris will be managed in compliance with regulations governing PCBs (40 CFR 761), and Environmental Compliance Guidance #27, *Lead-Based Paint (LBP) and Lead-Based Paint Debris Disposal* as applicable.

Based upon this RLCR and subject to concurrence by the Colorado Department of Public Health and Environment (CDPHE), the Security Cluster facilities are considered to be Type 1 facilities. To ensure that the facilities remain free of contamination and that RLC data remain valid, isolation controls will be established, and the facilities will be posted accordingly.

## **1 INTRODUCTION**

A Reconnaissance Level Characterization (RLC) was performed to enable compliant disposition and waste management of facilities 550, 761, 901, 762, 762A, 792, and 792A (a.k.a. Security Cluster). Because these facilities were anticipated to be Type 1 facilities, a PDS characterization was performed. All facilities surfaces were characterized in this RLC include the interior and exterior surfaces of the facilities (i.e., floors (slabs), walls, ceilings and roofs). Environmental media beneath and surrounding the facilities were not within the scope of this RLC Report (RLCR) and will be addressed using the Soil Disturbance Permit process.

As part of the Rocky Flats Environmental Technology Site (RFETS) Closure Project, numerous facilities will be removed. Among these are the Security Cluster facilities. The locations of these facilities are shown in Attachment A. These facilities no longer support the RFETS mission and need to be removed to reduce Site infrastructure, risks and/or operating costs.

Before the facilities can be removed, a Pre-Demolition Survey (PDS) must be conducted; this document presents the PDS results. The PDS was conducted pursuant to the Decontamination and Decommissioning Characterization Protocol (MAN-077-DDCP) and the Pre-Demolition Survey Plan for D&D Facilities (MAN-127-PDSP). The PDS built upon physical, chemical and radiological hazards identified in the facility specific Historical Site Assessment Reports.

### **1.1 Purpose**

The purpose of this report is to communicate and document the results of the RLC effort. PDSs are performed before building demolition to define the final radiological and chemical conditions of a facility. Final conditions are compared with the release limits for radiological and non-radiological contaminants. PDS results will enable project personnel to make final disposition decisions, develop related worker health and safety controls, and estimate waste volumes by waste types.

### **1.2 Scope**

This report presents the final radiological and chemical conditions of the Security Cluster facilities. Environmental media beneath and surrounding the facilities are not within the scope of this RLCR and will be addressed using the Soil Disturbance Permit process. Both facilities and environmental media will be dispositioned pursuant to the Rocky Flats Cleanup Agreement (RFCA).

### **1.3 Data Quality Objectives**

The Data Quality Objectives (DQOs) used in designing this RLC were the same DQOs identified in the Pre-Demolition Survey Plan for D&D Facilities (MAN-127-PDSP). Refer to section 2.0 of MAN-127-PDSP for these DQOs.

## **2 HISTORICAL SITE ASSESSMENT**

Facility specific Historical Site Assessments (HSAs) were conducted to understand facility histories and related hazards. The assessment consisted of facility walkdowns, interviews, and document review, including review of the Historical Release Report (refer to the D&D Characterization Protocol, MAN-077-DDCP). Results were used to identify data gaps and needs, and to develop radiological and chemical characterization packages. Results of the facility specific HSAs were documented in facility specific Historical Site Assessment Reports (HSAR). Refer to Attachment H, Historical Site Assessment Reports, for copies of the Security Cluster HSARs. In summary, the HSARs did not identify any known radiological or chemical hazards. Asbestos Containing Material may have been used during construction of the facilities.

## **3 RADIOLOGICAL CHARACTERIZATION AND HAZARDS**

### **3.1 Radiological Characterization**

Radiological characterization was performed to define the nature and extent of radioactive materials that may be present on or in the facilities. Measurements were performed to evaluate the contaminants of concern. Based on facility history, building walkdowns, and MARSSIM guidance, the facilities were broken down into survey areas, survey units, and classifications. A Radiological Characterization Package (refer to Attachment B) was developed during the planning phase that describes how the facilities were broken-down into survey units, the justification for the survey unit classifications, and the minimum sampling requirements per survey unit.

Radiological survey unit packages were developed for each survey unit in accordance with Radiological Safety Practices (RSP) 16.01, "Radiological Survey/Sampling Package Design, Preparation, Control, Implementation and Closure." Total Surface Activity (TSA), removable and scan measurements were collected in accordance with RSP 16.02 "Radiological Surveys of Surfaces and Structures." Radiological survey data were verified, validated and evaluated in accordance with RSP 16.04, "Radiological Survey/Sample Data Analysis." Quality Control measures were implemented thorough the survey and sampling process in accordance with RSP 16.05, "Radiological Survey/Sample Quality Control."

Radiological data, statistical analysis results, and survey locations are presented in Attachment D, Radiological Data Summaries and Survey Maps. Radiological survey packages are maintained in the Security Cluster Characterization Project files.

### **3.2 Radiological Hazards Summary**

The RLC (serving also as the Pre-Demolition Survey) confirmed that the Security Cluster facilities (i.e., all interior and exterior facility surfaces) do not contain radiological contamination above the surface contamination guidelines provided in DOE Order 5400.5 and the RFETS Radiological Control Manual. Isolation control postings are displayed at all entrances to the Security Cluster facilities to ensure no radioactive materials are introduced.

8



## 4 CHEMICAL CHARACTERIZATION AND HAZARDS

### 4.1 Chemical Characterization

Chemical characterization was performed to determine the nature and extent of chemical contamination that may be present on or in the Security Cluster facilities. Based upon a review of historical and process knowledge, visual inspections, and PDSP DQOs, additional sampling needs were determined. A Chemical Characterization Package (refer to Attachment C) was developed during the planning phase that describes sampling requirements and the justification for the sample locations and estimated sample numbers. Contaminants of concern included asbestos and beryllium. Refer to Attachment E, Chemical Summary Data and Sample Maps, for details on sample results and sample locations.

#### 4.1.1 Asbestos

Based on limited historical asbestos inspection data, an asbestos inspection and sampling of suspect asbestos containing material (ACM) was required for PDS. A CDPHE-certified asbestos inspector conducted the inspection and sampling in accordance with PRO-563-ACPR *Asbestos Characterization Protocol*, Revision 1. Potential ACM was identified for sampling at the discretion of the inspector.

Portals 762 and 792 are identical in construction and built at the same time. Samples collected in Portal 792 are considered representative of materials in Portal 762 and vice versa.

#### 4.1.2 Beryllium (Be)

There was not adequate information to conclude the absence of beryllium in the facilities, therefore limited biased sampling was performed in each facility per the PDSP. The limited, biased sampling design for these facilities is justified for the following reasons:

- Based on the Security Cluster historical site assessment reports, process knowledge of facility use and operations, personnel interviews, and facility walkdowns, there was no indication that beryllium was a contaminate of concern in these facilities.
- Although numerous site workers pass through buildings 762A (PACs 1) and 792A (PACs 3) on a daily basis, since these buildings were put into use - site practices have always required production building workers to remove protective clothing (e.g., yellow coveralls and tyvek suits) prior to leaving the Material Access Areas, and thus the Protected Area (PA). Therefore, the potential for spreading Be contamination into the PACs is minimal.
- Most production building workers shower and change into their street-cloths prior to leaving the PA, thus the potential for spreading Be contamination into the PACs is minimal.
- Tools and equipment are not routinely carried through the PACs buildings. Tools and equipment used in known Be areas are not removed from these areas until they are adequately sampled and determined to be suitable for release.

- The Security Guards that routinely occupied these facilities were not the same Security Guards that routinely accessed known Be areas.
- Due to the PAC's high traffic use, these facilities are routinely cleaned and mopped on a daily basis. Thus, the potential for Be contamination buildup is minimal.
- There has never been any known Be spills or events in these facilities.
- The areas sampled during this PDS effort were the areas having the highest potential for Be contamination - the high traffic areas of the floor.
- Other than the locations of known Be areas in the production buildings (e.g., 371, 707, 771, 776/777, and 779 Clusters), no other source terms for Be contamination were identified that would have potentially contaminated these buildings.

Based on the above rationale, it was determined that the Security Cluster facilities had a very low potential for Be contamination. A total of 14 samples were collected, all 14 sample results were  $<0.1 \mu\text{g}/100\text{cm}^2$ .

#### **4.1.3 RCRA/CERCLA Constituents [including metals and volatile and semi-volatile organic compounds (VOCs & SVOCs)]**

Based on the HSAR, there was no record of RCRA/CERCLA constituent operations or storage in the Security Cluster, therefore RCRA/CERCLA constituent sampling was not performed.

Sampling for lead in paint in the Security Cluster was not required. Environmental Waste Compliance Guidance #27, *Lead-based Paint (LBP) and Lead-based paint Debris Disposal*, states that LBP debris generated outside of currently identified high contamination areas shall be managed as non-hazardous (solid) wastes, and additional analysis for characteristics of hazardous waste derived from LBP is not a requirement for disposal.

#### **4.1.4 Polychlorinated Biphenyls (PCBs)**

Based on the HSAR, there was no record of PCB operations or storage in the Security Cluster, therefore PCB sampling was not performed. The Security Cluster facilities contain fluorescent light ballasts that may contain PCBs. Therefore, fluorescent light fixtures will be inspected to identify PCB ballasts during removal operations. PCB ballasts will be identified based on factors such as labeling (e.g., PCB-containing and non-PCB-containing), manufacturer, and date of manufacturing. All ballasts that do not indicate non-PCB-containing are assumed to be PCB-containing.

Historical data and process knowledge give no reason to suspect that any specialized paints or coatings containing PCBs were applied to any of the painted surfaces within the Security Cluster facilities. However, Environmental Waste Compliance Guidance #25, *Management of Polychlorinated Biphenyls (PCBs) in Paint and Other Bulk Product Waste During Facility Disposition*, has directed that applied dried paints, varnishes, waxes, or other similar coatings or sealants are acceptable for disposal (with notification) in a non-hazardous solid waste landfill as PCB Bulk Product Waste under 40 CFR 761.3 and 40 CFR 761.62 paragraph (b), and therefore, need not be sampled as long as restrictions outlined in 40 CFR 761.62 regarding their disposition are met. Current plans

are to dispose of demolition debris from the Security Cluster in an off-site, non-hazardous solid waste landfill as PCB Bulk Product Waste.

## **4.2 Chemical Hazards Summary**

Each facility was sampled for the presence of asbestos-containing material (ACM) and beryllium.

### **4.2.1 Asbestos**

The only area found to contain ACM was the roof flashing material of Buildings 762 and 792, in both friable and non-friable form. The asbestos containing felt in the roof flashing material is not tar impregnated and is considered friable. Asbestos containing materials will be removed and disposed of in compliance with Environmental Protection Agency (EPA) and Colorado Department of Public Health and Environment (CDPHE) regulations. Asbestos sample data and sample location maps are contained in Attachment E, Chemical Summary Data and Sample Maps. Estimated quantities of ACM are presented in Attachment F, Decommissioning Waste Types and Volume Estimates.

### **4.2.2 Beryllium**

Beryllium sample results of the Security Cluster facilities were all less than 0.1  $\mu\text{g}/100\text{cm}^2$ . Beryllium sample data and sample location maps are contained in Attachment E, Chemical Summary Data and Sample Maps.

### **4.2.3 RCRA/CERCLA Constituents**

Based on the HSAR, there was no record of RCRA/CERCLA constituent operations or storage in the Security Cluster, therefore RCRA/CERCLA constituents do not present a chemical hazards in the Security Cluster.

### **4.2.4 PCBs**

PCB ballasts may be found in the Security Cluster and will be removed and disposed of in accordance with site procedures prior to building demolition. It is not suspected that any specialized paints or coatings containing PCBs were applied to painted surfaces within the Security Cluster facilities, however, plans are to dispose of demolition debris in an off-site, non-hazardous solid waste landfill as PCB Bulk Product Waste.

## **5 PHYSICAL HAZARDS**

Physical hazards associated with the Security Cluster facilities consist of those common to standard industrial environments and include hazards associated with energized systems, utilities, and trips and falls. There are no unique hazards associated with the facilities. The facilities have been relatively well maintained and are in good physical condition, and therefore, do not present hazards associated with building deterioration. Physical hazards are controlled by the Site Occupational Safety and Industrial Hygiene Program, which is based on OSHA regulations, DOE orders, and standard industry practices.

## 6 DATA QUALITY ASSESSMENT

Data used in making management decisions for decommissioning of the Security Cluster, and consequent waste management, are of adequate quality to support the decisions documented in this report. The data presented in this report (Attachments A – G) were verified and validated relative to DOE quality requirements, applicable EPA guidance, and original DQOs of the project.

In summary, the V&V process corroborates that the following elements of the characterization process are adequate:

- ◆ the *number* of samples and surveys;
- ◆ the *types* of samples and surveys;
- ◆ the sampling/survey process as implemented “in the field”; and,
- ◆ the laboratory analytical process, relative to accuracy and precision considerations.

Details of the DQA are provided in Attachment G.

## 7 DECOMMISSIONING WASTE TYPES AND VOLUME ESTIMATES

The demolition and disposal of the Security Cluster will generate a variety of wastes. Attachment F presents the estimated waste volumes and waste type by facility. All wastes can be disposed of as sanitary waste, except asbestos containing material and PCB Bulk Product Waste. There is no radioactive or hazardous waste. Asbestos and PCB ballasts will be managed pursuant to Site asbestos and PCB abatement and waste management procedures.

## **8 FACILITY CLASSIFICATION AND CONCLUSIONS**

Based on the analysis of radiological, chemical and physical hazards, the Security Cluster facilities (i.e., 550, 761, 901, 762, 762A, 792, and 792A) are classified as RFCA Type 1 facilities pursuant to the RFETS Decommissioning Program Plan (DPP; K-H, 1999). The Type 1 classification is based on a review of historical and process knowledge, and newly acquired RLC data, and will be subject to concurrence by the Colorado Department of Public Health and the Environment (CDPHE).

The RLC of the Security Cluster was performed in accordance with the DDCP and PDSP; all PDSP DQOs were met, and all data satisfied the PDSP DQA criteria. These facilities do not contain radiological or hazardous wastes. All demolition debris will be managed in compliance with regulations governing PCBs (40 CFR 761), as applicable, in accordance with the Decommissioning Program Plan, Section 3.3.5. PCB ballasts and asbestos containing material will be removed and disposed of in compliance with EPA and CDPHE regulations. Environmental media beneath and surrounding the facilities will be addressed using the Soil Disturbance Permit process.

To ensure that the Type 1 facilities remain free of contamination and that RLC data remain valid, isolation controls have been established, and the facilities are posted accordingly.

## 9 REFERENCES

- ANSI-N323A-1997, Radiation Protection Instrumentation Test and Calibration.
- DOE/RFEO, CDPHE, EPA, 1996. Rocky Flats Cleanup Agreement (RFCA), July 19, 1996.
- DOE Order 5400.5, "Radiation Protection of the Public and the Environment."
- DOE Order 414.1A, "Quality Assurance."
- EPA, 1994. "The Data Quality Objective Process," EPA QA/G-4.
- K-H, 1997. "Kaiser-Hill Team Quality Assurance Program", Rev. 5, December, 1997.
- K-H, 1998. Facility Disposition Program Manual, MAN-076-FDPM, Rev. 1, September 1999.
- K-H, 1999. Decontamination and Decommissioning Characterization Protocol, MAN-077-DDCP, Rev. 1, June 19, 2000.
- K-H, 1999. Decommissioning Program Plan, June 21, 1999.
- K-H, 2000. Pre-Demolition Survey Plan, MAN-127-PDSP, Rev. 0, March 26, 2001.
- MARSSIM - Multi-Agency Radiation Survey and Site Investigation Manual, December 1997 (NUREG-1575, EPA 402-R-97-016).
- PRO-475-RSP-16.01, Radiological Survey/Sampling Package Design, Preparation, Control, Implementation, and Closure, September 30, 1999.
- PRO-476-RSP-16.02, Radiological Surveys of Surfaces and Structures, September 30, 1999.
- PRO-477-RSP-16.03, Radiological Samples of Building Media, September 30, 1999.
- PRO-478-RSP-16.04, Radiological Survey/Sample Data Analysis, September 30, 1999.
- PRO-479-RSP-16.05, Radiological Survey/Sample Quality Control, September, 30, 1999
- RFETS, Environmental Waste Compliance Guidance #25, Management of Polychlorinated Biphenyls (PCBs) in Paint and Other Bulk Product Waste During Facility Disposition.
- RFETS, Environmental Waste Compliance Guidance #27, Lead-Based Paint (LBP) and Lead-Based Paint Debris Disposal.
- RFETS, Historical Site Assessment Reports for Buildings 762, 762A, 792, 792A, 550, 761, and 901.

# ATTACHMENT A

## Facility Location Map

Best Available Copy

15

# Security Cluster Area

**EXPLANATION**  
Security Cluster Buildings



**Standard Map Features**  
Buildings and other structures



Solar Evaporation Ponds (SEP)



Lakes and ponds



Streams, ditches, or other drainage features



Fences and other barriers




Paved roads



Dirt roads



Not to be used for map display  
This map is for informational purposes only.  
It is not intended to be used for legal or  
other purposes. The user assumes all  
responsibility for any use of this map.  
Copyright 2001 by the U.S. Department of Energy



Scale = 1 : 5370  
1 inch represents approximately 448 feet



State Plane Coordinate Projection  
Colorado Central Zone  
Datum: NAD27

U.S. Department of Energy  
Rocky Flats Environmental Technology Site

GIS User: 300-366-7107


Prepared by:

**DynCorp**  
AN ENVIRONMENTAL TECHNOLOGY



March 15, 2001

MAP ID: 01-0231





# ATTACHMENT B

## Radiological Characterization Package



**Rocky Flats Environmental Technology Site**

**RADIOLOGICAL CHARACTERIZATION  
PACKAGE**

**SECURITY CLUSTER CLOSURE PROJECT**

**REVISION 0**

**March 1, 2001**

Prepared by: Jay M. Britten /

*Jay M. Britten* 2/27/01  
Radiological Engineer

Reviewed by: Duane Parsons /

*Duane Parsons* 2/27/01  
RISS Facility Characterization Coordinator

Reviewed by: Steve Luker /

*Steve Luker* 3/1/01  
Quality Assurance

Approved by: Vern Guthrie /

*Vern Guthrie* 3/1/01  
Closure Project Facility Manager

# Radiological Characterization Package

## Security Cluster (B762, B762A, B792, B792A, 550, 761, and 901)

Building: Security Cluster Last Updated: Date: 2/28/01 Time: 800 Initials: JMB

\* This characterization package was prepared in accordance with MAN-077-DDCP, D&D Characterization Protocols(07/26/00), and MAN-127-PDSP, Pre-Demolition Survey Plan for D&D Facilities (02/14/01).

\* PDSP Data Quality Objectives were used to develop this characterization package.

### Instructions:

1. Verify characterization activities are on the Plan-of-the-Day (POD).
2. Perform a Pre-Evolution Brief and/or Job Task Brief in accordance with the Site Conduct of Operations Manual.
3. Verify personnel have appropriate training for the applicable tasks they will be performing.
4. Comply with RWP requirements, if applicable.
5. Comply with JHA and facility PPE requirements, as applicable.
6. Inform the Facility Manager, or designee prior to starting characterization activities.
7. Follow applicable characterization and sampling procedures.
8. Notify Wackenhut Security (x2444) and the Shift Supervisor (x2914), and verify appropriate safety precautions/requirements are followed prior to accessing facility roofs.
9. Coordination with the Environmental Restoration Program organization will be required to further characterize underneath facility foundations and slabs prior to removal.
10. Collect and maintain all characterization paperwork in the Project File(s).
11. All radiological surveys shall be conducted in accordance with the sampling and instruction forms included in Security Cluster Package Identification numbers 01-0006, 01-0007, and 01-0008. Sample locations are denoted on scaled maps attached to each survey package.

### Class 1 Areas

Survey Area	Survey Unit	Class	Description	Total	Floor	Scan	MSA	Smears	Media	Characterization
N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	No Class 1 Areas Identified in this characterization unit. Historical Site Assessment and process knowledge indicate no need for this classification.
Class 1 Totals				0	0	0	0	0	0	

**Radiological Characterization Package**  
**Security Cluster (B762, B762A, B792, B792A, 550, 761, and 901)**

**Class 2 Areas**

Survey Area	Survey Unit	Class	Description	Total m	Floor m	Scan m	TSA	Smears	Media	Class Justification
N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	No Class 2 Areas identified in this characterization unit. Historical Site Assessment and process knowledge indicate no need for this classification.
<b>Class 2 Totals</b>				0	0	0	0	0	0	

**Radiological Characterization Package**  
**Security Cluster (B762, B762A, B792, B792A, 550, 761, and 901)**

**Class 3 Areas**

Survey Area	Survey Unit	Class	Description	Total sq ft	Floor sq ft	Sum sq ft	TSA	Remov	Metric	Comments/Qualification
A	SEC-A-001	3	Interior of B762, B762A, B792, and B792A	1820	516	182	15-random 45-biased Fifteen total sample points per building interior	15-random 45-biased Fifteen total sample points per building interior	0	Areas are not expected to contain, or have ever contained, any residual radioactivity greater than the DCGL <sub>w</sub> . Historical Site Assessment and process knowledge of this unit provide a high degree of confidence that no individual measurement will exceed the DCGL <sub>w</sub> . A 10% scan will be biased towards areas of greater potential for contamination (e.g., floors and lower walls). Additional biased measurements have been prescribed and will be collected to ensure all building surfaces are adequately characterized. These additional biased measurements are above and beyond requirements set forth in the RFETS PDSP.
A	SEC-A-002	3	Interiors of B550, B761, and B901 [1st Floor - Walls, Floor, Ceiling] [2nd Floor - Walls, Floor, & Ceiling] [3rd Floor - Walls, Floor, & Ceiling]	661	86	67	15-random 30-biased Fifteen total sample points per building interior	15-random 30-biased Fifteen total sample points per building interior	0	Areas are not expected to contain, or have ever contained, any residual radioactivity greater than the DCGL <sub>w</sub> . Historical Site Assessment and process knowledge of this unit provide a high degree of confidence that no individual measurement will exceed the DCGL <sub>w</sub> . A 10% scan will be biased towards areas of greater potential for contamination (e.g., floors and lower walls). Additional biased measurements have been prescribed and will be collected to ensure all building surfaces are adequately characterized. These additional biased measurements are above and beyond requirements set forth in the RFETS PDSP.
B	SEC-B-003	3	Exterior of B762, B762A, B792, and B792A [including roof], AND Exterior of B550, B761, B901 [including roof]	2613	137	262	15-random 90-biased 15 total sample points per building exterior	15-random 90-biased 15 total sample points per building exterior	0	Areas are not expected to contain, or have ever contained, any residual radioactivity greater than the DCGL <sub>w</sub> . Historical Site Assessment of this unit provides a high degree of confidence that no individual measurement will exceed the DCGL <sub>w</sub> . A 10% scan will be biased towards areas of greater potential for contamination (e.g., lower walls & roof areas). Additional biased measurements have been prescribed and will be collected to ensure all building surfaces are adequately characterized. These additional biased measurements are above and beyond requirements set forth in the RFETS PDSP.
<b>Class 3 Totals</b>				<b>5094</b>	<b>739</b>	<b>511</b>	<b>210</b>	<b>210</b>	<b>0</b>	
<b>All Class Areas</b>				<b>5094</b>	<b>739</b>	<b>511</b>	<b>210</b>	<b>210</b>	<b>0</b>	

\* Larger numbers of biased TSA and Removable sample locations provided to adequately characterize facility surfaces.

**Radiological Characterization Package**  
**Security Cluster (B762, B762A, B792, B792A, 550, 761, and 901)**

**Non-Impacted Areas**

Survey Area	Survey Unit	Class	Description	Total m <sup>2</sup>	Floor m <sup>2</sup>	Scanning	TSA	Smears	Media	Justification
N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	No Non-Impacted Areas identified in this characterization unit. Historical Site Assessment and process knowledge indicate no need for this classification.
<b>Non-Impacted Totals</b>				0	0	0	0	0	0	

# ATTACHMENT C

## Chemical Characterization Package



**Rocky Flats Environmental Technology Site**

**CHEMICAL CHARACTERIZATION PACKAGE**

**SECURITY BUILDING CLUSTER CLOSURE PROJECT**

**REVISION 1**

**February 20, 2001**


Prepared by:

  
Industrial Hygiene

Prepared by:

  
Environmental Compliance

Reviewed by:

  
Quality Assurance

Reviewed by:

 2/21/01  
RISS Facility Characterization Coordinator

Approved by:

 2/23/01  
Closure Project Facility Manager



## CHEMICAL CHARACTERIZATION PACKAGE

**BUILDING(s): SECURITY CLUSTER (550, 761, 901, 762, 762A, 792, 792A)**

\* This characterization package was prepared in accordance with MAN-077-DDCP, D&D Characterization Protocols, and MAN-127-PDSP, Pre-Demolition Survey Plan for D&D Facilities.

\* PDSP Data Quality Objectives were used to develop this characterization package.

**Instructions:**

1. Verify characterization activities are on the Plan-of-the-Day (POD).
2. Perform a Pre-Evolution Brief and/or Job Task Brief in accordance with the Site Conduct of Operations Manual.
3. Verify personnel have appropriate training for the applicable tasks they will be performing.
4. Comply with RWP requirements, if applicable.
5. Comply with JHA and facility PPE requirements, as applicable.
6. Inform the Facility Manager, or designee prior to starting characterization activities.
7. Follow applicable characterization and sampling procedures.
8. Notify Wackenhut Security (x2444) and the Shift Supervisor (x2914), and verify appropriate safety precautions/requirements are followed prior to accessing facility roofs.
9. Coordination with the Environmental Restoration Program organization will be required to further characterize underneath facility foundations and slabs prior to removal.
10. Collect and maintain all characterization paperwork in the Project File(s), and all electronic data in the appropriate D&D RISS subdirectory.

<b>ASBESTOS</b>		
<b>Sample Location</b>	<b>Estimated Number of Samples</b>	<b>Sample location and justification/rational</b>
550, 761 & 901	10 per building	Asbestos inspections have not been performed. As a result, a comprehensive invasive inspection must be performed in accordance with PRO-563-ACPR, Asbestos Characterization Procedure. Suspect materials include drywall, base cove, floor insulation and roof.
762 & 792	11 per building	Asbestos inspections have not been performed. As a result, a comprehensive invasive inspection must be performed in accordance with PRO-563-ACPR, Asbestos Characterization Procedure. Suspect materials include window caulking, roof and flashing, ceiling tile, floor tile, base cove and drywall.
762A & 792A	24 per building	Asbestos inspections have not been performed. As a result, a comprehensive invasive inspection must be performed in accordance with PRO-563-ACPR, Asbestos Characterization Procedure. Suspect materials include ceiling tile, drywall, base cove, roof and flashing, pipe insulation, linoleum, exterior soffit texture, transite, window caulking.
<b>Total Samples:</b>	100	The exact sample numbers and locations will not be determined until a comprehensive, invasive inspection is performed in accordance with 40 CFR Part 763, Subpart E. Sample locations will be specified on sample maps during characterization efforts. Samples will be obtained in accordance with PRO-563-ACPR, Asbestos Characterization Procedure and 40 CFR 763.

<b>BERYLLIUM</b>		
<b>Sample Location</b>	<b>Number of Samples (smears)</b>	<b>Sample location and justification/rational</b>
550, 761, 901, 762, 762A, 792, 792A	14 - biased	There is no documented supporting data or process history that proves beryllium was not used or stored in these buildings. Therefore, two biased

		samples from each of the seven building will be obtained. Buildings have similar history and can be treated as one area.
<b>Total Samples:</b>	14	Samples will be obtained at locations specified on sample map(s) in accordance with PRO-536-BCPR, Beryllium Characterization Procedure. Biased sample locations will correspond with the most probable areas of dust accumulation (including beryllium dust), assuming airborne deposition.

<b>LEAD</b>		
<b>Sample Location</b>	<b>Number of Samples</b>	<b>Sample location and justification/rational</b>
Security Cluster, all locations	0	Lead sampling is not required for Security Cluster buildings. All paint will remain a part of the infrastructure during demolition and therefore does not require sampling per Environmental Waste Compliance Guidance No. 27, Lead Based Paint (LBP) and LBP Debris Disposal. In addition, these buildings were constructed in 1982, 1983, and 1989, and lead based paint is not probable. Sampling for lead for IH requirements will be at the discretion of the demolition contractor.
<b>Total Samples:</b>	0	

<b>RCRA/CERCLA CONSTITUENTS</b>		
<b>Sample Location</b>	<b>Number of Samples</b>	<b>Sample location and justification/rational</b>
Security Cluster	0	No hazardous activities that may have resulted in RCRA or CERCLA constituents occurred in the Security Cluster buildings, therefore sampling for RCRA/CERCLA constituents is not required. <b>Note: These buildings do contain materials that may need to be managed as Regulated Waste during D&amp;D activities including mercury thermostats, fluorescent light bulbs, circuit boards, and HVAC systems. Care will need to be taken to ensure these wastes are managed properly.</b>
<b>Total Samples:</b>	0	

<b>PCBs</b>		
<b>Sample Location</b>	<b>Number of Samples</b>	<b>Sample location and justification/rational</b>
Security Cluster	0	The Security Cluster buildings were constructed in 1982, 1983, and 1989. PCB contamination in the structural debris is not probable. No sampling is required. <b>Note: These buildings do contain materials that may need to be managed as Regulated Waste during D&amp;D activities, such as light ballasts. Care will need to be taken to ensure these wastes are managed properly.</b>
<b>Total Samples:</b>	0	

- \* PCB ballasts, fluorescent light bulbs, potential mercury switches in thermostats, and mercury vapor light bulbs shall be removed prior to demolition.

# ATTACHMENT D

## Radiological Data Summaries and Survey Maps

## **SURVEY UNIT DATA SUMMARY: SEC-A-001**

**Survey Unit Description:**

**Interior of 762, 762A, 792 and 792A**

## Survey Unit SEC-A-001 Data Summary

### Total Surface Activity Measurements

	60	60
	Number Required	Number Obtained
MIN	-11.7	dpm/100 cm <sup>2</sup>
MAX	26.4	dpm/100 cm <sup>2</sup>
MEAN	0.9	dpm/100 cm <sup>2</sup>
STD DEV	8.3	dpm/100 cm <sup>2</sup>
TRANSURANIC DCGL <sub>w</sub>	100	dpm/100 cm <sup>2</sup>

### Removable Activity Measurements

	60	60
	Number Required	Number Obtained
MIN	-0.9	dpm/100 cm <sup>2</sup>
MAX	9.1	dpm/100 cm <sup>2</sup>
MEAN	1.2	dpm/100 cm <sup>2</sup>
STD DEV	2.2	dpm/100 cm <sup>2</sup>
TRANSURANIC DCGL <sub>w</sub>	20	dpm/100 cm <sup>2</sup>

29

# Survey Unit SEC-A-001 Total Surface Activity Results

Manufacturer:	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	7	8	11	12	19	34	35
Serial #:	3114	1546	1546	1366	3114	1241	1546
Cal Due Date:	5/6/01	5/3/01	5/3/01	5/6/01	5/6/01	8/26/01	5/3/01
Analysis Date:	3/26/01	3/26/01	3/27/01	3/27/01	3/27/01	3/29/01	3/29/01
Alpha Eff. (cid):	0.22	0.228	0.228	0.204	0.22	0.214	0.228
Alpha Bkgd (cpm)	2.0	2.0	0.7	0.7	0.0	0.7	1.3
Sample Time (min)	1.5	1.5	1.5	1.5	1.5	1.5	1.5
LAB Time (min)	1.5	1.5	1.5	1.5	1.5	1.5	1.5
MDC (dpm/100cm <sup>2</sup> )	33.5	32.3	22.7	25.4	9.1	24.2	27.8

Sample Location Number	Instrument ID#:	Sample Gross Counts (cpm)	LAB Gross Counts (cpm)	Sample Net Activity (dpm/100cm <sup>2</sup> )
1	11	2.7	2.0	-2.5
2	11	3.3	3.3	0.1
3	35	2.0	0.7	-5.6
4	11	9.3	2.7	26.4
5	35	2.0	0.7	-5.6
6	12	2.7	3.4	-2.8
7	11	2.7	2.0	-2.5
8	35	4.0	2.7	3.2
9	11	4.7	2.0	6.3
10	35	6.0	4.0	12.0
11	11	2.7	4.7	-2.5
12	35	2.0	2.7	-5.6
13	35	1.3	3.3	-8.7
14	12	3.3	2.7	0.1
15	12	2.0	1.3	-6.2
16	35	2.7	2.0	-2.5
17	35	1.3	2.0	-8.7
18	7	4.7	4.0	6.5
19	8	2.7	0.7	-2.5
20	19	0.7	4.7	-11.7
21	11	0.7	1.3	-11.3
22	11	3.3	4.0	0.1
23	19	4.7	4.0	6.5
24	35	2.0	5.3	-5.6
25	35	4.7	0.7	6.3
26	35	1.3	2.0	-8.7
27	35	2.7	2.0	-2.5
28	35	2.7	5.3	-2.5
29	35	1.3	2.7	-8.7
30	35	2.7	1.3	-2.5
31	7	1.3	4.7	-9.0
32	7	4.0	4.7	3.3
33	8	7.3	2.7	17.7
34	8	3.4	3.3	0.6
35	8	0.7	3.3	-11.3
36	8	2.0	1.3	-5.6
37	7	6.7	3.3	15.6
38	7	3.3	8.0	0.1
39	7	0.7	7.3	-11.7
40	8	3.3	1.3	0.1
41	8	3.3	0.7	0.1
42	7	4.7	4.0	6.5
43	7	5.3	7.3	9.2
44	11	2.7	2.0	-2.5
45	19	6.0	7.3	12.4
46	11	2.7	0.7	-2.5
47	19	5.7	4.3	11.0

# **Survey Unit SEC-A-001 Total Surface Activity Results**

Manufacturer:	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	7	8	11	12	19	34	35
Serial #:	3114	1546	1546	1366	3114	1241	1546
Cal Due Date:	5/6/01	5/3/01	5/3/01	5/6/01	5/6/01	8/26/01	5/3/01
Analysis Date:	3/26/01	3/26/01	3/27/01	3/27/01	3/27/01	3/29/01	3/29/01
Alpha Eff. (cld):	0.22	0.228	0.228	0.204	0.22	0.214	0.228
Alpha Bkgd (cpm)	2.0	2.0	0.7	0.7	0.0	0.7	1.3
Sample Time (min)	1.5	1.5	1.5	1.5	1.5	1.5	1.5
LAB Time (min)	1.5	1.5	1.5	1.5	1.5	1.5	1.5
MDC (dpm/100cm <sup>2</sup> )	33.5	32.3	22.7	25.4	9.1	24.2	27.8

Sample Location Number	Instrument ID#:	Sample Gross Counts (cpm)	LAB Gross Counts (cpm)	Sample Net Activity (dpm/100cm <sup>2</sup> )
48	19	4.0	4.7	3.3
49	12	3.4	5.4	0.6
50	11	8.0	3.3	20.7
51	11	2.7	2.0	-2.5
52	11	2.7	0.7	-2.5
53	11	4.0	3.3	3.2
54	11	4.7	3.3	6.3
55	19	4.7	7.0	6.5
56	19	4.0	5.3	3.3
57	19	1.3	0.7	-9.0
58	19	6.0	3.3	12.4
59	19	4.7	6.3	6.5
60	19	6.0	4.7	12.4
			Average LAB	3.3
			MIN	-11.7
			MAX	26.4
			MEAN	0.9
			SD	8.3
			Transuranic DCGL <sub>w</sub>	100

## **QC DATA**

QC-2	7	7.3	6.0	18.3
QC-3	12	4.7	1.3	7.0
QC-10	34	0.7	2.0	-12.0
			Average LAB	3.1
			MIN	-12.0
			MAX	18.3
			MEAN	4.4
			SD	15.3
			Transuranic DCGL <sub>w</sub>	100

# Survey Unit SEC-A-001 Smear Results

Manufacturer:	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4
Instrument ID#:	1	2	3	4	13	14	15	16	25
Serial #:	830	833	1157	770	830	833	1157	770	1157
Cal Due Date:	8/12/01	7/23/01	8/27/01	7/18/01	8/12/01	7/23/01	8/27/01	7/18/01	8/27/01
Analysis Date:	3/28/01	3/28/01	3/28/01	3/28/01	3/29/01	3/29/01	3/29/01	3/29/01	3/26/01
Alpha Eff. (c/d):	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33
Alpha Bkgd (cpm)	0	0	0	0.3	0.0	0.0	0.0	0.1	0.1
Sample Time (min)	2	2	2	2	2	2	2	2	2
Bkgd Time (min)	10	10	10	10	10	10	10	10	10
MDC (dpm/100cm <sup>2</sup> )	4.5	4.5	4.5	8.8	4.5	4.5	4.5	7.0	7.0

Sample Location Number	Instrument ID#	Gross Counts (cpm)	Net Activity (dpm/100 cm <sup>2</sup> )
1	3	0.0	0.0
2	3	0.0	0.0
3	13	0.0	0.0
4	3	1.0	3.0
5	16	1.0	2.7
6	4	0.0	-0.9
7	2	0.0	0.0
8	15	0.0	0.0
9	2	2.0	6.1
10	14	1.0	3.0
11	1	0.0	0.0
12	15	0.0	0.0
13	16	1.0	2.7
14	2	1.0	3.0
15	1	0.0	0.0
16	13	0.0	0.0
17	14	0.0	0.0
18	15	3.0	9.1
19	16	2.0	5.8
20	4	0.0	-0.9
21	2	0.0	0.0
22	4	0.0	-0.9
23	2	1.0	3.0
24	15	0.0	0.0
25	15	1.0	3.0
26	16	0.0	-0.3
27	13	2.0	6.1
28	13	0.0	0.0
29	14	0.0	0.0
30	13	1.0	3.0
31	15	1.0	3.0
32	25	0.0	-0.3
33	25	0.0	-0.3
34	16	1.0	2.7
35	25	0.0	-0.3
36	16	2.0	5.8
37	13	0.0	0.0
38	15	1.0	3.0
39	14	0.0	0.0
40	25	0.0	-0.3
41	16	1.0	2.7
42	15	0.0	0.0

32



# Survey Unit SEC-A-001 Smear Results

Manufacturer:	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4
Instrument ID#:	1	2	3	4	13	14	15	16	25
Serial #:	830	833	1157	770	830	833	1157	770	1157
Cal Due Date:	8/12/01	7/23/01	8/27/01	7/18/01	8/12/01	7/23/01	8/27/01	7/18/01	8/27/01
Analysis Date:	3/28/01	3/28/01	3/28/01	3/28/01	3/29/01	3/29/01	3/29/01	3/29/01	3/28/01
Alpha Eff. (c/d):	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33	0.33
Alpha Bkgd (cpm)	0	0	0	0.3	0.0	0.0	0.0	0.1	0.1
Sample Time (min)	2	2	2	2	2	2	2	2	2
Bkgd Time (min)	10	10	10	10	10	10	10	10	10
MDC (dpm/100cm <sup>2</sup> )	4.5	4.5	4.5	8.8	4.5	4.5	4.5	7.0	7.0


Sample Location Number	Instrument ID#	Gross Counts (cpm)	Net Activity (dpm/100 cm <sup>2</sup> )
43	25	0.0	-0.3
44	4	0.0	-0.9
45	1	0.0	0.0
46	2	0.0	0.0
47	1	1.0	3.0
48	2	0.0	0.0
49	3	0.0	0.0
50	1	0.0	0.0
51	3	0.0	0.0
52	1	0.0	0.0
53	1	0.0	0.0
54	4	1.0	2.1
55	3	0.0	0.0
56	2	0.0	0.0
57	1	1.0	3.0
58	4	0.0	-0.9
59	3	0.0	0.0
60	2	0.0	0.0
		MIN	-0.9
		MAX	9.1
		MEAN	1.2
		SD	2.2
		Transuranic DCGL <sub>w</sub>	20

# DEMOLITION SURVEY FOR SECURITY CLASS. 2


Survey Area: A Survey Unit: SEC-A-001 Classification: 3  
 Building: 762, 762A, 792, 792A  
 Survey Unit Description: Interiors  
 Total Area: 1820 sq. m. Total Floor Area: 516 sq. m.

## Building 762A

→ Scan Survey Areas



## Building 762




**SURVEY MAP LEGEND**

- Scan & TSA Location
- ◆ Scan, TSA & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

Under the United States Government and Editor M. H. Co., we DynCorp M&E, and any agency thereof, we or any of our employees, officers, agents or legal, or otherwise our liability or responsibility for the accuracy, completeness, or timeliness of any information, opinions, profits, or losses derived, or expected that in we would not be liable for any errors or omissions.

Scan Survey Information  
 Survey Instrument ID #s: 3, 10, 11, 20, 21, 22  
 RCT ID #s: 2, 5, 8



U.S. Department of Energy  
 Rocky Flats Environmental Technology Site  
 Prepared by: GRS Dept. 203-000-7709 Prepared for:  
**DynCorp**  
 THE ART OF TECHNOLOGY  
 March 6, 2001

SEC-A-001

PAGE 1 OF 2


34

# PRE-DEMOLITION SURVEY FOR SECURITY CLUSTER


Survey Area: A      Survey Unit: SEC-A-001      Classification: 3  
 Building: 762, 762A, 792, 792A  
 Survey Unit Description: Interiors  
 Total Area: 1820 sq. m.      Total Floor Area: 516 sq. m.

## Building 792A

= Scan Survey Areas



## Building 792





**SURVEY MAP LEGEND**

- Scanner & TSA Location
- Scanner, TSA & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

Under the United States Government and/or Lockheed Martin Co., and DynCorp MDC, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

Scan Survey Information  
 Survey Instrument ID #s: 9, 10, 11, 20, 21, 22, 31, 32  
 RCT ID #s: 76, 8



U.S. Department of Energy  
 Rocky Flats Environmental Technology Site

Prepared by: GSA Dept. 950-880-7700 Prepared for:  
**DynCorp**  
 THE ART OF TECHNOLOGY

MAP ID: 6282101-0221      Date: 6/20/01

# ATTACHMENT E

## Chemical Data Summaries and Sample Maps

### 9.1..1.1.1.1 Asbestos Data Summary

Sample Number	Material Sampled & Location	Analytical Results
762A-03222001-05-001	762A, 2' x 2' white ceiling tile with small groove & random dot – bathroom	Not Detected
762A-03222001-05-002	762A, 2' x 2' white ceiling tile with small groove & random dot – bathroom	Not Detected
762A-03222001-05-003	762A, Drywall & tape joint compound – bathroom	Not Detected
762A-03222001-05-004	762A, Beige linoleum – bathroom	Not Detected
762A-03222001-05-005	762A, Brown base cove with mastic (drywall paper stuck to sample) – janitor's closet	Not Detected
762A-03222001-05-006	762A, Beige linoleum – room 106	Not Detected
762A-03222001-05-007	762A, Drywall mud only – room 103	Not Detected
762A-03222001-05-008	762A, Drywall & tape joint compound – room 109	Not Detected
792A-03192001-05-001	792A, 2' x 2' white ceiling tile with large groove & random dot – janitor's closet	Not Detected
792A-03192001-05-002	792A, Yellow linoleum – janitor's closet	Not Detected
792A-03192001-05-003	792A, Yellow linoleum – janitor's closet	Not Detected
792A-03192001-05-004	792A, Base cove with yellow mastic (drywall paper stuck to sample) – janitor's closet	Not Detected
792A-03192001-05-005	792A, Drywall & tape joint compound – janitor's closet	Not Detected
792A-03192001-05-006	792A, Drywall & tape joint compound – entrance to janitor's closet	Not Detected
792A-03192001-05-007	792A, 2' x 2' white ceiling tile with large groove & random dot – bathroom	Not Detected
792A-03192001-05-008	792A, Caulk on exterior ducts (red painted beige) – exterior ducts on west side	Not Detected
792A-03192001-05-009	792A, Beige exterior sheeting with styrofoam beneath – exterior, west center	Not Detected
792A-03192001-05-010	792A, Beige exterior sheeting with styrofoam beneath – exterior, west side, south end	Not Detected
792A-03192001-05-011	792A, Beige exterior sheeting with styrofoam beneath – exterior, west side, north end	Not Detected
792-03202001-05-001	792, 2' x 2' white ceiling tile with small groove & random dot – bathroom	Not Detected
792-03202001-05-002	792, 2' x 2' white ceiling tile with small groove & random dot – bathroom	Not Detected
792-03202001-05-003	792, Drywall and tape joint compound – main doorway entrance	Not Detected
792-03202001-05-004	792, Drywall and tape joint compound – bathroom	Not Detected
792-03202001-05-005	792, Black base cove and mastic – bathroom entrance	Not Detected
792-03202001-05-006	792, Drywall and tape joint compound – exterior soffit on south end	Not Detected
901-03012001-05-001	901, Drywall and tape joint compound – SW corner	Not Detected
901-03012001-05-002	901, Drywall & tape joint compound – East wall	Not Detected
901-03012001-05-003	901, Drywall & tape joint compound – West wall	Not Detected
901-03012001-05-004	901, Brown base cove mastic – SE corner	Not Detected
901-03012001-05-005	901, Brown base cove mastic – NW corner	Not Detected
901-03012001-05-006	901, Roof core sample – West end	Not Detected

38

SEC-A-001

PAGE 1 OF 2

**SURVEY MAP LEGEND**

Advisories Sample Location

Bay/Blind Sample Location

Lead Sample Location

SCBA/CEBCLA Sample Location

PCBS Sample Location

Notes: The United States Government and its Contractors shall not be held responsible for any errors or omissions in this map. The map is for informational purposes only and should not be used for any other purpose.

Open/Inaccessible Areas

Areas in Another Survey Unit

0 10 20 30

0 10 20 30

METERS

FEET

1 inch = 24 feet 1 grid sq. = 1 sq. m.








**dynacorp**

U.S. Department of Energy

Radiation Physics Environmental Technology Site

Report No. 142881481-4231

DATE: 11/11/01



**PRE-DEMOLITION SURVEY FOR SECURITY CLUSTER**

Survey Area: A

Survey Unit: SEC-A-001

Classification: N/A

Building: 762, 762A, 792, 792A

Survey Unit Description: Interiors

Total Area: 1820 sq. m.


Total Floor Area: 516 sq. m.

Sample Number	Material Sampled & Location	Analytical Results
901-03012001-05-007	901, Roof core sample – center	Not Detected
550-03012001-05-001	550, Drywall & tape joint compound – West wall	Not Detected
550-03012001-05-002	550, Drywall & tape joint compound – South wall	Not Detected
550-03012001-05-003	550, Drywall & tape joint compound – North wall	Not Detected
550-03012001-05-004	550, Brown base cove mastic – South wall	Not Detected
550-03012001-05-005	550, Gray window caulk – South window	Not Detected
550-03012001-05-006	550, Roof core sample	Not Detected
550-03012001-05-007	550, Roof core sample	Not Detected
761-03012001-05-001	761, Drywall & tape joint compound – North wall	Not Detected
761-03012001-05-002	761, Drywall & tape joint compound – East wall	Not Detected
761-03012001-05-003	761, Drywall & tape joint compound – West wall	Not Detected
761-03012001-05-004	761, Brown base cove mastic – Northeast corner	Not Detected
761-03012001-05-005	761, Gray window caulk – Southeast corner	Not Detected
761-03012001-05-006	761, Roof core sample	Not Detected
761-03012001-05-007	761, Roof core sample	Not Detected
762-03282001-05-001	762, Roof flashing core sample	60% chrysotile in felt; 20% chrysotile in tar
762-03282001-05-002	762, Roof core sample	Trace chrysotile – point count trace


# **PRE-DEMOLITION SURVEY FOR SECURITY CLUSTER**

Survey Area: A      Survey Unit: SEC-A-001      Classification: N/A  
 Building: 762, 762A, 792, 792A  
 Survey Unit Description: Interiors  
 Total Area: 1820 sq. m.      Total Floor Area: 516 sq. m.

## **Building 792A**



## **Building 792**








<b>SURVEY MAP LEGEND</b> (A) Asbestos Sample Location (B) Beryllium Sample Location (C) Lead Sample Location (D) RCRA/CERCLA Sample Location (E) PCBs Sample Location	Under the United States Government or Kaiser 198 Co., nor DynCorp 1987, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or timeliness of any information, opinions, products, or services furnished, or represents that its use would not infringe patents owned by others.	N ↑	0 FEET 30 0 METERS 10 1 inch = 24 feet 1 grid sq. = 1 sq. m.	U.S. Department of Energy Rocky Flats Environmental Technology Site <b>DynCorp</b> THE ART OF TECHNOLOGY Prepared by: GRS Dept. 363-898-779 Prepared for: MAP ID: 1920101-0201 March 8, 2001
--	--	-----	--	---








# PRE-DEMOLITION SURVEY FOR SECURITY CLUSTER

Survey Area: A      Survey Unit: SEC-A-002      Classification: N/A  
 Building: 550, 761, 901  
 Survey Unit Description: Interiors (1st floor < 8 ft.)  
 Total Area: 661 sq. m.      Total Floor Area: 86 sq. m.






## Building 550



## Building 761



## Building 901




<b>SURVEY MAP LEGEND</b> (A) Asbestos Sample Location (B) Beryllium Sample Location (C) Lead Sample Location (R) RACER/CIA Sample Location (P) PCB/S Sample Location (O) Open/Inaccessible Area (A) Area in Another Survey Unit	Under the United States Government and Kaiser Aluminum Co., Inc. use DynCorp M&E, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.	0 30 FEET 0 10 METERS 1 inch = 24 feet 1 grid sq. = 1 sq. m.	U.S. Department of Energy Rocky Plate Environmental Technology Site Prepared by: GNS Dept. 262-888-7769 Prepared for: <b>DynCorp</b> THE ART OF TECHNOLOGY MAP ID: 020201-0221 March 8, 2001
--	--	--	---

41


# PRE-DEMOLITION SURVEY FOR SECURITY CLUSTER

Survey Area: B      Survey Unit: SEC-B-003      Classification: N/A  
 Building: 762, 762A, 792, 792A, 550, 761, 901  
 Survey Unit Description: Exteriors  
 Total Area: 2613 sq. m.      Total Floor Area: 137 sq. m.


## Building 762




## Building 792



## Building 762 Walls





## Building 792 Walls



Building 762A Exit Area

## Building 762A




## SURVEY MAP LEGEND

- Asbestos Sample Location
- Beryllium Sample Location
- Lead Sample Location
- ROB/CERCLA Sample Location
- PCBS Sample Location

Neither the United States Government nor Ebasco INC. Co., nor DynCorp LLC, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

- Open/Inaccessible Area
- Area in Another Survey Unit



U.S. Department of Energy  
 Rocky Flats Environmental Technology Site  
 Prepared by: QRS Dept. 353-000-7765 Prepared for:  
**DynCorp**  
 THE ART OF TECHNOLOGY  
 MAP ID: 1720101-0321 March 8, 2001

## Survey Unit SEC-A-002 Data Summary

### Total Surface Activity Measurements

	45	45
	Number Required	Number Obtained
MIN	-7.7	dpm/100 cm <sup>2</sup>
MAX	57.6	dpm/100 cm <sup>2</sup>
MEAN	15.9	dpm/100 cm <sup>2</sup>
STD DEV	14.1	dpm/100 cm <sup>2</sup>
TRANSURANIC DCGL <sub>w</sub>	100	dpm/100 cm <sup>2</sup>

### Removable Activity Measurements

	45	45
	Number Required	Number Obtained
MIN	-0.6	dpm/100 cm <sup>2</sup>
MAX	6.1	dpm/100 cm <sup>2</sup>
MEAN	0.4	dpm/100 cm <sup>2</sup>
STD DEV	1.8	dpm/100 cm <sup>2</sup>
TRANSURANIC DCGL <sub>w</sub>	20	dpm/100 cm <sup>2</sup>


## Survey Unit SEC-A-002 Total Surface Activity Results

Manufacturer:	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	7	8	9	10	11	12
Serial #:	1254	1366	1254	N/A	N/A	N/A
Cal Due Date:	5/20/01	5/6/01	5/20/01	N/A	N/A	N/A
Analysis Date:	3/20/01	3/20/01	3/20/01	N/A	N/A	N/A
Alpha Eff. (c/d):	0.227	0.204	0.227	N/A	N/A	N/A
Alpha Bkgd (cpm)	2.0	2.0	2.0	N/A	N/A	N/A
Sample Time (min)	1.5	1.5	1.5	N/A	N/A	N/A
LAB Time (min)	1.5	1.5	1.5	N/A	N/A	N/A
MDC (dpm/100cm <sup>2</sup> )	32.5	36.2	32.5	N/A	N/A	N/A


Sample Location Number	Instrument ID#:	Sample Gross Counts (cpm)	LAB Gross Counts (cpm)	Sample Net Activity (dpm/100cm <sup>2</sup> )
1	8	5.3	4.0	14.9
2	8	4.0	1.3	8.5
3	8	3.3	2.7	5.1
4	8	10.7	3.3	41.4
5	8	4.0	1.3	8.5
6	8	1.3	1.3	-4.8
7	7	6.0	2.0	16.4
8	7	6.7	2.7	19.5
9	7	8.0	4.0	25.3
10	8	6.0	2.0	18.3
11	8	4.7	7.3	11.9
12	8	7.3	3.3	24.7
13	8	3.3	2.0	5.1
14	7	5.3	1.3	13.4
15	8	2.6	2.0	1.6
16	8	2.7	2.7	2.1
17	7	9.3	2.0	31.0
18	7	1.3	4.0	-4.3
19	7	1.3	2.7	-4.3
20	7	5.3	1.3	13.4
21	8	3.3	2.0	5.1
22	8	9.3	2.0	34.5
23	7	4.7	2.0	10.7
24	8	4.0	1.3	8.5
25	8	6.7	2.7	21.8
26	7	12.0	1.3	42.9
27	7	12.7	3.3	46.0
28	8	14.0	0.7	57.6
29	8	5.3	2.0	14.9
30	7	3.3	0.7	4.5
31	8	3.3	2.7	5.1
32	8	8.0	2.0	28.2
33	7	4.0	3.3	7.6
34	7	6.7	1.3	19.5
35	7	6.0	2.0	16.4
36	7	7.3	3.3	22.2
37	8	7.3	2.0	24.7
38	8	0.7	3.3	-7.7

# PRE-DEMOLITION SURVEY FOR SECURITY CLUSTER


Survey Area: B Survey Unit: SEC-B-003 Classification: N/A  
 Building: 762, 762A, 792, 792A, 550, 761, 901  
 Survey Unit Description: Exteriors  
 Total Area: 2613 sq. m. Total Floor Area: 137 sq. m.




## Building 550




## Building 761



## Building 792A



## Building 901




### SURVEY MAP LEGEND

- Asbestos Sample Location
- Beryllium Sample Location
- Lead Sample Location
- RCRA/CERCLA Sample Location
- PCBS Sample Location

Neither the United States Government nor Enxior H&E Co., nor DynCorp M&E, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

- Open/Inaccessible Area
- Area in Another Survey Unit



U.S. Department of Energy  
 Rocky Flats Environmental Technology Site

Prepared by: GHS Dept. 303-886-7769 Prepared for:

**DynCorp**  
 THE ART OF TECHNOLOGY

ROF ID: 62291271-2221 March 8, 2001

45

## **SURVEY UNIT DATA SUMMARY: SEC-A-002**

**Survey Unit Description:**

**Interior of 550, 761 and 901**

## Survey Unit SEC-A-002 Total Surface Activity Results

Manufacturer:	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	7	8	9	10	11	12
Serial #:	1254	1366	1254	N/A	N/A	N/A
Cal Due Date:	5/20/01	5/6/01	5/20/01	N/A	N/A	N/A
Analysis Date:	3/20/01	3/20/01	3/20/01	N/A	N/A	N/A
Alpha Eff. (c/d):	0.227	0.204	0.227	N/A	N/A	N/A
Alpha Bkgd (cpm)	2.0	2.0	2.0	N/A	N/A	N/A
Sample Time (min)	1.5	1.5	1.5	N/A	N/A	N/A
LAB Time (min)	1.5	1.5	1.5	N/A	N/A	N/A
MDC (dpm/100cm <sup>2</sup> )	32.5	36.2	32.5	N/A	N/A	N/A

Sample Location Number	Instrument ID#:	Sample Gross Counts (cpm)	LAB Gross Counts (cpm)	Sample Net Activity (dpm/100cm <sup>2</sup> )
39	8	6.0	1.3	18.3
40	8	6.7	1.3	21.8
41	8	7.3	0.7	24.7
42	8	2.7	2.0	2.1
43	8	4.0	0.7	8.5
45	7	5.3	2.7	13.4
			Average LAB	2.3
			MIN	-7.7
			MAX	57.6
			MEAN	15.9
			SD	14.1
			Transuranic DCGL <sub>w</sub>	100

### QC DATA

QC-23	9	3.3	2.0	5.7
QC-9	9	4.7	3.3	11.9
QC-35	9	8.0	0.7	26.4
			Average LAB	2.0
			MIN	5.7
			MAX	26.4
			MEAN	14.7
			SD	10.6
			Transuranic DCGL <sub>w</sub>	100

## Survey Unit SEC-A-002 Smear Results

Manufacturer:	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4
Instrument ID#:	1	2	3	4	5	6
Serial #:	767	833	830	N/A	N/A	N/A
Cal Due Date:	4/11/01	7/23/01	8/12/01	N/A	N/A	N/A
Analysis Date:	3/20/01	3/20/01	3/20/01	N/A	N/A	N/A
Alpha Eff. (c/d):	0.33	0.33	0.33	N/A	N/A	N/A
Alpha Bkgd (cpm)	0.2	0	0.2	N/A	N/A	N/A
Sample Time (min)	2	2	2	N/A	N/A	N/A
Bkgd Time (min)	10	10	10	N/A	N/A	N/A
MDC (dpm/100cm <sup>2</sup> )	8.0	4.5	8.0	N/A	N/A	N/A

Sample Location Number	Instrument ID#	Gross Counts (cpm)	Net Activity (dpm/100 cm <sup>2</sup> )
1	2	0.0	0.0
2	3	0.0	-0.6
3	3	2.0	5.5
4	2	0.0	0.0
5	3	0.0	-0.6
6	2	0.0	0.0
7	2	0.0	0.0
8	1	0.0	-0.6
9	1	1.0	2.4
10	3	0.0	-0.6
11	1	1.0	2.4
12	2	0.0	0.0
13	3	0.0	-0.6
14	3	1.0	2.4
15	3	0.0	-0.6
16	2	0.0	0.0
17	3	0.0	-0.6
18	3	0.0	-0.6
19	1	0.0	-0.6
20	1	0.0	-0.6
21	1	0.0	-0.6
22	1	1.0	2.4
23	2	0.0	0.0
24	1	0.0	-0.6
25	1	0.0	-0.6
26	3	0.0	-0.6
27	2	0.0	0.0
28	1	1.0	2.4
29	1	0.0	-0.6
30	1	0.0	-0.6
31	2	0.0	0.0
32	2	1.0	3.0
33	3	0.0	-0.6
34	1	0.0	-0.6
35	2	2.0	6.1
36	2	0.0	0.0
37	3	0.0	-0.6
38	3	0.0	-0.6
39	3	0.0	-0.6
40	1	0.0	-0.6
41	2	0.0	0.0
42	2	0.0	0.0
43	1	2.0	5.5
44	3	0.0	-0.6
45	2	0.0	0.0
		MIN	-0.6
		MAX	6.1
		MEAN	0.4
		SD	1.8
		Transuranic DCGL <sub>w</sub>	20




# DEMOLITION SURVEY FOR SECURITY CLUS


Survey Area: A Survey Unit: SEC-A-002 Classification: 3  
 Building: 550, 761, 901  
 Survey Unit Description: Interiors (1st floor < 8 ft.)  
 Total Area: 661 sq. m. Total Floor Area: 86 sq. m.

= Scan survey Areas


## Building 550



## Building 761



## Building 901




### SURVEY MAP LEGEND

- Sensor & TEA Location
- ◆ Sensor, TEA & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

Under the United States Government and Ender Hill Co., we DynCorp LLC, our agency, and our employees, we warrant that the information, opinions, products, or services we provide are accurate, complete, and reliable, and that we warrant that we will not knowingly provide false information.

Scan Survey Information  
 Survey Instrument ID # (s): 389 789  
 RCT ID # (s): 345



U.S. Department of Energy  
 Rocky Flats Environmental Technology Site  
 Prepared by: GRS Dept. 200-000-7707 Prepared for:  
**DynCorp**  
 THE ART OF TECHNOLOGY  
 MAP ID: 0020101-001 Rev 6, 2001

## **SURVEY UNIT DATA SUMMARY: SEC-B-003**

### **Survey Unit Description:**

**Exterior of 762, 762A, 792, 792A, 550, 761 and 901**

## Survey Unit SEC-B-003 Data Summary

### Total Surface Activity Measurements

105	105
Number Required	Number Obtained

MIN	-18.7	dpm/100 cm <sup>2</sup>
MAX	96.2	dpm/100 cm <sup>2</sup>
MEAN	23.4	dpm/100 cm <sup>2</sup>
STD DEV	25.0	dpm/100 cm <sup>2</sup>

TRANSURANIC DCGL <sub>w</sub>	100	dpm/100 cm <sup>2</sup>
----------------------------------	-----	-------------------------

### Removable Activity Measurements

105	105
Number Required	Number Obtained

MIN	-0.9	dpm/100 cm <sup>2</sup>
MAX	9.1	dpm/100 cm <sup>2</sup>
MEAN	1.2	dpm/100 cm <sup>2</sup>
STD DEV	2.3	dpm/100 cm <sup>2</sup>

TRANSURANIC DCGL <sub>w</sub>	20	dpm/100 cm <sup>2</sup>
----------------------------------	----	-------------------------

# Survey Unit SEC-B-003 Total Surface Activity Results

Manufacturer:	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	7	8	10	11	12	19
Serial #:	1546	1254	1366	3114	1546	1254
Cal Due Date:	5/3/01	5/20/01	5/6/01	5/6/01	5/3/01	5/20/01
Analysis Date:	3/21/01	3/21/01	3/21/01	3/22/01	3/22/01	3/22/01
Alpha Eff. (c/d):	0.228	0.227	0.204	0.22	0.228	0.227
Alpha Bkgd (cpm)	2.0	0.7	1.3	2.7	2.0	2.0
Sample Time (min)	1.5	1.5	1.5	1.5	1.5	1.5
LAB Time (min)	1.5	1.5	1.5	1.5	1.5	1.5
MDC (dpm/100cm <sup>2</sup> )	32.3	22.8	31.0	37.5	32.3	32.5

Manufacturer:	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	21	22	23	24	31	32	33
Serial #:	3114	1546	3114	1546	3114	1546	1241
Cal Due Date:	5/6/01	5/3/01	5/6/01	5/3/01	5/6/01	5/3/01	8/26/01
Analysis Date:	3/23/01	3/23/01	3/26/01	3/26/01	3/27/01	3/27/01	3/28/01
Alpha Eff. (c/d):	0.22	0.228	0.22	0.228	0.220	0.228	0.214
Alpha Bkgd (cpm)	0.7	1.3	2.0	2.0	0.0	0.7	0.7
Sample Time (min)	1.5	1.5	1.5	1.5	1.5	1.5	1.5
LAB Time (min)	1.5	1.5	1.5	1.5	1.5	1.5	1.5
MDC (dpm/100cm <sup>2</sup> )	23.5	27.8	33.5	32.3	9.1	22.7	24.2

Sample Location Number	Instrument ID#:	Sample Gross Counts (cpm)	LAB Gross Counts (cpm)	Sample Net Activity (dpm/100cm <sup>2</sup> )
1	12	8.0	2.7	17.1
2	33	2.0	2.7	-9.8
3	33	21.3	10.7	80.4
4	22	7.7	2.7	15.8
5	11	4.0	2.0	-0.5
6	7	14.7	8.7	46.5
7	12	2.0	4.4	-9.2
8	19	4.0	4.7	-0.5
9	21	11.3	6.0	32.7
10	11	7.3	2.7	14.5
11	21	12.0	2.7	35.9
12	33	15.3	2.0	52.3
13	32	5.3	3.3	5.2
14	23	8.0	2.7	17.7
15	10	8.0	2.7	19.1
16	19	14.7	4.0	46.7
17	8	12.0	4.7	34.8
18	8	20.7	7.3	73.1
19	11	0.0	0.7	-18.7
20	12	2.0	3.3	-9.2
21	12	3.3	0.7	-3.5
22	12	4.0	4.7	-0.5
23	11	6.7	2.0	11.8
24	12	4.0	3.3	-0.5
25	11	2.0	1.3	-9.6
26	12	6.7	3.3	11.4
27	11	4.0	2.0	-0.5
28	12	7.3	4.7	14.0
29	11	4.0	2.0	-0.5
30	33	15.3	1.3	52.3
31	33	7.3	2.7	14.9
32	12	2.0	4.7	-9.2
33	11	3.3	1.3	-3.7
34	11	1.4	1.3	-12.3
35	12	9.3	2.7	22.8
36	19	8.0	4.7	17.2
37	11	6.7	2.7	11.8
38	12	5.3	4.0	5.2
39	11	3.3	2.7	-3.7
40	12	4.0	6.0	-0.5
41	11	2.7	3.3	-6.4
42	12	2.7	6.0	-6.2
43	33	16.0	0.7	55.6

# Survey Unit SEC-B-003 Total Surface Activity Results

Manufacturer:	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	7	8	10	11	12	19
Serial #:	1546	1254	1366	3114	1546	1254
Cal Due Date:	5/3/01	5/20/01	5/6/01	5/6/01	5/3/01	5/20/01
Analysis Date:	3/21/01	3/21/01	3/21/01	3/22/01	3/22/01	3/22/01
Alpha Eff. (c/d):	0.228	0.227	0.204	0.22	0.228	0.227
Alpha Bkgd (cpm)	2.0	0.7	1.3	2.7	2.0	2.0
Sample Time (min)	1.5	1.5	1.5	1.5	1.5	1.5
LAB Time (min)	1.5	1.5	1.5	1.5	1.5	1.5
MDC (dpm/100cm <sup>2</sup> )	32.3	22.8	31.0	37.5	32.3	32.5

Manufacturer:	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	21	22	23	24	31	32	33
Serial #:	3114	1546	3114	1546	3114	1546	1241
Cal Due Date:	5/6/01	5/3/01	5/6/01	5/3/01	5/6/01	5/3/01	6/26/01
Analysis Date:	3/23/01	3/23/01	3/26/01	3/26/01	3/27/01	3/27/01	3/28/01
Alpha Eff. (c/d):	0.22	0.228	0.22	0.228	0.220	0.228	0.214
Alpha Bkgd (cpm)	0.7	1.3	2.0	2.0	0.0	0.7	0.7
Sample Time (min)	1.5	1.5	1.5	1.5	1.5	1.5	1.5
LAB Time (min)	1.5	1.5	1.5	1.5	1.5	1.5	1.5
MDC (dpm/100cm <sup>2</sup> )	23.5	27.8	33.5	32.3	9.1	22.7	24.2

Sample Location Number	Instrument ID#:	Sample Gross Counts (cpm)	LAB Gross Counts (cpm)	Sample Net Activity (dpm/100cm <sup>2</sup> )
44	24	6.0	3.3	8.3
45	24	4.7	2.0	2.6
46	23	6.7	2.0	11.8
47	24	12.7	1.3	37.7
48	21	11.3	5.3	32.7
49	23	6.0	4.0	8.6
50	23	5.3	4.0	5.4
51	19	4.0	1.3	-0.5
52	33	22.0	10.7	83.6
53	33	24.7	10.7	96.2
54	22	4.0	0.7	-0.5
55	22	6.7	2.7	11.4
56	21	22.7	4.7	84.5
57	33	21.3	6.7	80.4
58	33	22.3	6.7	85.0
59	33	22.7	7.3	86.9
60	21	4.7	6.0	2.7
61	31	6.0	6.7	8.6
62	22	5.3	4.0	5.2
63	21	12.7	3.3	39.1
64	21	6.7	8.7	11.8
65	21	12.0	6.0	35.9
66	11	9.3	3.3	23.6
67	11	11.3	2.7	32.7
68	12	9.3	2.7	22.8
69	12	8.7	2.0	20.2
70	12	11.3	8.7	31.6
71	11	12.0	4.7	35.9
72	12	8.0	4.7	17.1
73	11	12.7	2.7	39.1
74	12	10.0	2.7	25.9
75	11	5.3	4.7	5.4
76	11	9.3	2.7	23.6
77	11	7.7	3.3	16.3
78	12	12.7	6.0	37.7
79	11	9.3	2.7	23.6
80	7	12.7	3.3	37.7
81	7	8.7	4.0	20.2
82	10	10.7	5.3	32.3
83	10	6.7	6.0	12.7
84	7	8.0	5.3	17.1
85	10	14.7	5.3	51.9
86	10	10.7	6.0	32.3

# Survey Unit SEC-B-003 Total Surface Activity Results

Manufacturer:	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	7	8	10	11	12	19
Serial #:	1546	1254	1368	3114	1546	1254
Cal Due Date:	5/3/01	5/20/01	5/6/01	5/6/01	5/3/01	5/20/01
Analysis Date:	3/21/01	3/21/01	3/21/01	3/22/01	3/22/01	3/22/01
Alpha Eff. (c/d):	0.228	0.227	0.204	0.22	0.228	0.227
Alpha Bkgd (cpm)	2.0	0.7	1.3	2.7	2.0	2.0
Sample Time (min)	1.5	1.5	1.5	1.5	1.5	1.5
LAB Time (min)	1.5	1.5	1.5	1.5	1.5	1.5
MDC (dpm/100cm <sup>2</sup> )	32.3	22.8	31.0	37.5	32.3	32.5

Manufacturer:	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra	NE Electra
Model:	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6	DP-6
Instrument ID#:	21	22	23	24	31	32	33
Serial #:	3114	1546	3114	1546	3114	1546	1241
Cal Due Date:	5/6/01	5/3/01	5/6/01	5/3/01	5/6/01	5/3/01	8/26/01
Analysis Date:	3/23/01	3/23/01	3/26/01	3/26/01	3/27/01	3/27/01	3/28/01
Alpha Eff. (c/d):	0.22	0.228	0.22	0.228	0.220	0.228	0.214
Alpha Bkgd (cpm)	0.7	1.3	2.0	2.0	0.0	0.7	0.7
Sample Time (min)	1.5	1.5	1.5	1.5	1.5	1.5	1.5
LAB Time (min)	1.5	1.5	1.5	1.5	1.5	1.5	1.5
MDC (dpm/100cm <sup>2</sup> )	23.5	27.8	33.5	32.3	9.1	22.7	24.2

Sample Location Number	Instrument ID#:	Sample Gross Counts (cpm)	LAB Gross Counts (cpm)	Sample Net Activity (dpm/100cm <sup>2</sup> )
87	10	6.7	7.3	12.7
88	10	8.0	4.0	19.1
89	10	17.3	3.3	64.7
90	7	6.7	4.7	11.4
91	10	7.3	4.0	15.7
92	10	6.0	2.7	9.3
93	10	12.0	2.7	38.7
94	7	10.0	7.3	25.9
95	10	13.3	4.0	45.1
96	7	15.3	6.0	49.1
97	10	9.3	2.7	25.5
98	7	9.3	6.0	22.8
99	7	18.0	6.0	60.9
100	10	7.3	2.7	15.7
101	7	6.0	3.3	8.3
102	7	14.7	4.0	48.5
103	7	7.3	4.0	14.0
104	7	9.3	3.3	22.8
105	7	14.0	5.3	43.4

Average LAB	4.1
MIN	-18.7
MAX	96.2
MEAN	23.4
SD	25.0
Transuranic DCGL <sub>w</sub>	100

## QC DATA

QC-2	10	8.7	2.7	20.9
QC-3	10	12.0	1.3	35.9
QC-3	12	13.3	8	40.5
QC-3	19	8.0	7.3	17.2
QC-3	11	6.0	2.7	8.3
QC-10	11	4.0	2.7	-0.5

Average LAB	4.1
MIN	-0.5
MAX	40.6
MEAN	20.4
SD	15.7
Transuranic DCGL <sub>w</sub>	100

# Survey Unit SEC-B-003 Smear Results

Manufacturer:	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4
Instrument ID#:	1	2	3	4	5	6	13
Serial #:	830	833	767	770	830	833	767
Cal Due Date:	8/12/01	7/23/01	4/11/01	7/18/01	8/12/01	7/23/01	4/11/01
Analysis Date:	3/21/01	3/21/01	3/21/01	3/21/01	3/21/01	3/21/01	3/23/01
Alpha Eff. (c/d):	0.33	0.33	0.33	0.33	0.33	0.33	0.33
Alpha Bkgd (cpm)	0.1	0.2	0.2	0.1	0.2	0.0	0.3
Sample Time (min)	2	2	2	2	2	2	2
Bkgd Time (min)	10	10	10	10	10	10	10
MDC (dpm/100cm <sup>2</sup> )	7.0	8.0	8.0	7.0	8.0	4.5	8.8

Manufacturer:	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4
Instrument ID#:	14	17	18	25	26	27	28
Serial #:	770	830	833	830	833	1157	770
Cal Due Date:	7/18/01	8/12/01	7/23/01	8/12/01	7/23/01	8/27/01	7/18/01
Analysis Date:	3/23/01	3/26/01	3/26/01	3/29/01	3/29/01	3/29/01	3/29/01
Alpha Eff. (c/d):	0.33	0.33	0.33	0.33	0.33	0.33	0.33
Alpha Bkgd (cpm)	0.2	0	0.1	0.0	0.0	0.0	0.1
Sample Time (min)	2	2	2	2	2	2	2
Bkgd Time (min)	10	10	10	10	10	10	10
MDC (dpm/100cm <sup>2</sup> )	8.0	4.5	7.0	4.5	4.5	4.5	7.0

Sample Location Number	Instrument ID#	Gross Counts (cpm)	Net Activity (dpm/100 cm <sup>2</sup> )
1	13	0.0	-0.9
2	26	2.0	5.8
3	26	0.0	0.0
4	14	1.0	2.4
5	6	0.0	0.0
6	1	0.0	-0.3
7	13	1.0	2.1
8	26	0.0	0.0
9	5	1.0	2.4
10	14	1.0	2.4
11	14	0.0	-0.6
12	2	0.0	-0.6
13	17	1.0	3.0
14	25	0.0	0.0
15	1	0.0	-0.3
16	5	0.0	-0.6
17	3	0.0	-0.6
18	4	0.0	-0.3
19	5	0.0	-0.6
20	6	0.0	0.0
21	5	1.0	2.4
22	6	0.0	0.0
23	13	0.0	-0.9
24	14	1.0	2.4
25	15	0.0	0.0
26	6	0.0	0.0
27	5	0.0	-0.6
28	5	0.0	-0.6
29	14	0.0	-0.6
30	3	0.0	-0.6
31	4	0.0	-0.3
32	14	2.0	5.5
33	14	0.0	-0.6
34	5	2.0	5.5
35	13	0.0	-0.9
36	6	0.0	0.0
37	14	0.0	-0.6
38	13	1.0	2.1
39	6	1.0	3.0
40	14	0.0	-0.6
41	5	2.0	5.5
42	13	0.0	-0.9
43	1	2.0	5.8
44	18	0.0	-0.3
45	17	0.0	0.0
46	25	0.0	0.0
47	18	1.0	2.7
48	6	0.0	0.0
49	17	0.0	0.0
50	17	1.0	3.0
51	27	0.0	0.0
52	27	1.0	3.0
53	25	3.0	9.1
54	13	0.0	-0.9
55	6	1.0	3.0
56	5	0.0	-0.6
57	28	1.0	2.7
58	25	2.0	6.1
59	26	1.0	3.0
60	5	0.0	-0.6
61	18	1.0	2.7
62	6	1.0	3.0
63	13	2.0	5.2
64	14	1.0	2.4
65	13	0.0	-0.9
66	5	0.0	-0.6
67	14	0.0	-0.6
68	13	1.0	2.1
69	6	0.0	0.0
70	5	0.0	-0.6

# Survey Unit SEC-B-003 Smear Results

Manufacturer:	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4
Instrument ID#:	1	2	3	4	5	6	13
Serial #:	830	833	767	770	830	833	767
Cal Due Date:	8/12/01	7/23/01	4/11/01	7/18/01	8/12/01	7/23/01	4/11/01
Analysis Date:	3/21/01	3/21/01	3/21/01	3/21/01	3/21/01	3/21/01	3/23/01
Alpha Eff. (c/d):	0.33	0.33	0.33	0.33	0.33	0.33	0.33
Alpha Bkgd (cpm):	0.1	0.2	0.2	0.1	0.2	0.0	0.3
Sample Time (min):	2	2	2	2	2	2	2
Bkgd Time (min):	10	10	10	10	10	10	10
MDC (dpm/100cm <sup>2</sup> ):	7.0	8.0	8.0	7.0	8.0	4.5	8.8

Manufacturer:	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4	SAC-4
Instrument ID#:	14	17	18	25	26	27	28
Serial #:	770	830	833	830	833	1157	770
Cal Due Date:	7/18/01	8/12/01	7/23/01	8/12/01	7/23/01	8/27/01	7/18/01
Analysis Date:	3/23/01	3/26/01	3/26/01	3/29/01	3/29/01	3/29/01	3/29/01
Alpha Eff. (c/d):	0.33	0.33	0.33	0.33	0.33	0.33	0.33
Alpha Bkgd (cpm):	0.2	0	0.1	0.0	0.0	0.0	0.1
Sample Time (min):	2	2	2	2	2	2	2
Bkgd Time (min):	10	10	10	10	10	10	10
MDC (dpm/100cm <sup>2</sup> ):	8.0	4.5	7.0	4.5	4.5	4.5	7.0

Sample Location Number	Instrument ID#	Gross Counts (cpm)	Net Activity (dpm/100 cm <sup>2</sup> )
71	5	2.0	5.5
72	13	0.0	-0.9
73	14	2.0	5.5
74	5	0.0	-0.6
75	14	0.0	-0.6
76	6	0.0	0.0
77	6	0.0	0.0
78	13	0.0	-0.9
79	6	1.0	3.0
80	3	1.0	2.4
81	4	0.0	-0.3
82	1	0.0	-0.3
83	4	0.0	-0.3
84	2	1.0	2.4
85	3	0.0	-0.6
86	2	0.0	-0.6
87	2	1.0	2.4
88	2	1.0	2.4
89	1	0.0	-0.3
90	3	2.0	5.5
91	4	0.0	-0.3
92	1	0.0	-0.3
93	1	1.0	2.7
94	2	0.0	-0.6
95	3	0.0	-0.6
96	4	2.0	5.8
97	2	0.0	-0.6
98	3	0.0	-0.6
99	4	0.0	-0.3
100	2	0.0	-0.6
101	1	0.0	-0.3
102	1	1.0	2.7
103	2	1.0	2.4
104	3	1.0	2.4
105	4	2.0	5.8
		MIN	-0.9
		MAX	9.1
		MEAN	1.2
		SD	2.3
		Transuranic DCGL <sub>w</sub>	20




# DE-DEMOLITION SURVEY FOR SECURITY CLASSIFIER


Survey Area: B Survey Unit: SEC-B-003 Classification: 3  
 Building: 762, 762A, 792, 792A, 550, 761, 901  
 Survey Unit Description: Exteriors  
 Total Area: 2813 sq. m. Total Floor Area: 137 sq. m.

= Scan  
 Survey  
 Areas


Building 762



Building 792



Building 762A




## SURVEY MAP LEGEND

- Scan & TSA Location
- Scan, TSA & Sample Location
- Open/Inaccessible Area
- Area in Another Survey Unit

Neither the United States Government nor Ecolab Inc. Co., nor DynCorp M&E, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

Scan Survey Information  
 Survey Instrument ID #s: 7, 8, 10, 32, 8, 20  
 RCT ID #s: 3, 4, 5, 10




1 inch = 24 feet 1 grid sq. = 1 sq. m.

U.S. Department of Energy  
 Rocky Flats Environmental Technology Site  
 Prepared by: GRS Dept. 303-433-7799 Prepared for:  
**DynCorp**  
 THE ART OF TECHNOLOGY  
 MAP ID: 5025101-0021  
 Sheet A 202

# DEMOLITION SURVEY FOR SECURITY CLASSIFICATION

Survey Area: B Survey Unit: SEC-B-003 Classification: 3  
 Building: 762, 762A, 792, 792A, 550, 761, 901  
 Survey Unit Description: Exteriors  
 Total Area: 2613 sq. m. Total Floor Area: 137 sq. m.

= Scan Survey Areas



**SURVEY MAP LEGEND**

- ② Sensor & TEA Location
- ◇ Sensor, TEA & Sample Location
- Open/Inaccessible Area
- ▤ Area in Another Survey Unit

Neither the United States Government nor Eikon Inc. Co., nor DynCorp LLC, nor any agency thereof, nor any of their employees, makes any warranty, expressed or implied, or assumes any liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.

Scan Survey Information  
 Survey Instrument ID #s: 7, 9, 16, 32, 8, 20  
 ECT ID #s: 34, 5, 16



1 inch = 24 feet 1 grid sq. = 1 sq. m.

U.S. Department of Energy  
 Rocky Flats Environmental Technology Site  
 Prepared by: GRS Dept. 262-682-7700 Prepared for:  
**DynCorp**  
 THE ART OF TECHNOLOGY  
 MAP ID: 0201101-0201 Rev. A 2001

SEC-B-003

PAGE 2 OF 2

58


Beryllium Data Summary

Sample Number	Sample Location	Result (ug/100 cm <sup>2</sup> )
901-03132001-05-001	901, Doorway of first floor	< 0.1
901-03132001-05-002	901, Window sill on third floor	< 0.1
761-03132001-05-001	761, Doorway of first floor	< 0.1
761-03132001-05-002	761, Landing on second floor	< 0.1
761-03132001-05-003	Field Blank	< 0.1
761-03132001-05-004	Field Blank	< 0.1
550-03132001-05-001	550, Doorway of first floor	< 0.1
550-03132001-05-002	550, Landing on second floor	< 0.1
762A-03222001-05-001	762A, Entrance to utility closet	< 0.1
762A-03222001-05-002	762A, East security turnstile	< 0.1
762-03222001-05-001	762, Bathroom	< 0.1
762-03222001-05-002	762, On top of radiator – east wall	< 0.1
792-03202001-05-001	792, Bathroom	< 0.1
792-03202001-05-002	792, Top of electrical panel	< 0.1
792A-03222001-05-001	792A, North doorway	< 0.1
792A-03222001-05-002	792A, South doorway	< 0.1



# PRE-DEMOLITION SURVEY FOR SECURITY CLUSTER

Survey Area: A      Survey Unit: SEC-A-001      Classification: N/A  
 Building: 762, 762A, 792, 792A  
 Survey Unit Description: Interiors  
 Total Area: 1820 sq. m.      Total Floor Area: 516 sq. m.

## Building 762A



## Building 762










<b>SURVEY MAP LEGEND</b> Asbestos Sample Location Beryllium Sample Location Lead Sample Location ROBACERCLA Sample Location PCBS Sample Location	Under the United States Government or Excess HR Co., we DynCorp M&T, nor any agency thereof, nor any of our employees, make any warranty, express or implied, or assume any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.		0      FEET      30  0      METERS      10 1 inch = 24 feet    1 grid sq. = 1 sq. m.	U.S. Department of Energy Rocky Plate Environmental Technology Site Prepared by: G&S Dept. 362-005-7789 Prepared for: <b>DynCorp</b> THE ART OF TECHNOLOGY MAP ID: 0200101-0231      March A 2001
---	---	--	---	--



# PRE-DEMOLITION SURVEY FOR SECURITY CLUSTER

Survey Area: A      Survey Unit: SEC-A-001      Classification: N/A  
 Building: 762, 762A, 792, 792A  
 Survey Unit Description: Interiors  
 Total Area: 1820 sq. m.      Total Floor Area: 516 sq. m.

## Building 792A



## Building 792




<b>SURVEY MAP LEGEND</b> Asbestos Sample Location Beryllium Sample Location Lead Sample Location RCRA/CERCLA Sample Location PCBS Sample Location	Whether the United States Government or Knorr 141 Co., or DynCorp LLC, or any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that it or we would not infringe privately owned rights.		<p>0 30  <b>FEET</b></p> <p>0 10  <b>METERS</b></p> <p>1 inch = 24 feet 1 grid sq. = 1 sq. m.</p>	<p>U.S. Department of Energy                  Rocky Flats Environmental Technology Site</p> <p>Prepared by: QRS Dept. 363-886-778 Prepared for:  <b>DynCorp</b>                  THE ART OF TECHNOLOGY</p> <p>NOV 1993                  March 8, 2001</p>
--	---	--	---	---


# PRE-DEMOLITION SURVEY FOR SECURITY CLUSTER

Survey Area: A      Survey Unit: SEC-A-002      Classification: N/A  
 Building: 550, 761, 901  
 Survey Unit Description: Interiors (1st floor < 8 ft.)  
 Total Area: 661 sq. m.      Total Floor Area: 86 sq. m.


## Building 550



## Building 761



## Building 901



<b>SURVEY MAP LEGEND</b> (A) Asbestos Sample Location (B) Beryllium Sample Location (C) Lead Sample Location (D) RCRA/CERCLA Sample Location (E) PCBs Sample Location (F) Open/Inaccessible Area (G) Area in Another Survey Unit	Whether the United States Government or Ebasco Inc. Co., or DynCorp MFT, or any agency thereof, or any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights.	N 0 30 FEET 0 10 METERS 1 inch = 24 feet 1 grid sq. = 1 sq. m.	U.S. Department of Energy Rocky Plate Environmental Technology Site Prepared by: G23 Dept. 353-666-770 Prepared for: <b>DynCorp</b> THE ART OF TECHNOLOGY MAP ID: 0299101-0231 March 8, 2001
---	---	---	---

## ATTACHMENT F

# Decommissioning Waste Types and Volume Estimates

**Attachment F – Decommissioning Waste Types and Volumes Estimates**

Facility	Concrete <sup>1</sup> (cu ft)	Wood <sup>1</sup> (cu ft)	Metal <sup>1</sup> (cu ft)	Corrugated/ Sheet Metal <sup>1</sup> (cu ft)	Wall Board <sup>1</sup> (cu ft)	ACM (sq. ft)	Other Waste (cu ft)
550	1,874	None	75	None	4	None	Glass – 67 Insulation – 75
761	2121	None	100	None	4	None	Glass – 67 Insulation – 75
901	2121	None	100	None	4	None	Glass – 67 Insulation – 75
762	1069	None	5	None	50	Roof Flashing - 193	Glass – 20 Insulation – 311 Acoustical Tile – 24
762A	6929	None	1500	None	410	None	Glass – 15 Ridged Insulation – 1211 Fiberglass Insulation – 1687 Acoustical Tile – 203 Raised Floor Panels – 52
792	896	None	5	None	44	Roof Flashing - 193	Glass – 20 Insulation – 272 Acoustical Tile – 20
792A	3118	None	675	None	185	None	Glass – 7 Ridged Insulation – 545 Fiberglass Insulation – 759 Acoustical Tile – 91

(1) Materials are assumed to be PCB Bulk Product Waste.



## ATTACHMENT G

### Data Quality Assessment (DQA) Detail

## **DATA QUALITY ASSESSMENT (DQA) – SECURITY CLUSTER RLCR**

### **INTRODUCTION**

Data used in making management decisions for decommissioning and waste management must be of adequate quality to support the decisions. Adequate data quality for decisionmaking is required by the Kaiser-Hill Team Quality Assurance Program (K-H, 1997, §7.1.4 and 7.2.2), as well as by the customer (DOE, RFFO; Order O 414.1, Quality Assurance, §4.b.(2)(b)). Regulators and the public also expect decisions and data that are technically and legally defensible. Verification and validation of the data ensure that data used in decisions resulting from the Pre-Demolition Survey (PDS) are usable and defensible.

Verification and validation (V&V) of this RLCR are the primary components of the DQA. V&V constitutes the cornerstone of the DQA, because statistical tests and material background determinations relative to decision-making for radiological survey units were not implemented nor required. Instead, measurement results were compared, on a one-to-one basis, with release criteria given in DOE Order 5400.5. The PDS results could, theoretically, be used to conduct Sign Tests for decisions, but because all individual measurements were less than the DCGL<sub>w</sub>, the survey units meet release criteria without further data reduction. This DQA supports conclusions in the report through implementation of the guidelines taken from the following MARSSIM sections:

- §4.9, Quality Control
- §8.2, Data Quality Assessment
- §9.0, Quality Assurance & Quality Control
- Appendix E, Assessment Phase of the Data Life Cycle
- Appendix N, Data Validation using Data Descriptors

DQA was performed on measurement and sample results obtained from the Survey Units listed Table G-1. These Survey Units are traceable to specific building locations.

### **VERIFICATION OF RESULTS**

Verification ensures that data produced and used by the project are documented and traceable, per quality requirements. Verification consisted of reviewing the project's data relative to the following subsets, for each unique Survey Unit:

- Radiological
  - scans (total surface contamination)
  - surveys (TSA and removable)
- Chemical
  - asbestos

ANALYTE	# Samples Required (incl. Media; Real & QC Samples)	# Taken (Real & QC Samples) <sup>B</sup>	Project Decisions (Conclusions) & Uncertainty	Comments (RIN, Analytical Method, Qualifications, etc.)
Asbestos <sup>A</sup> • Bldg 550 • Bldg 761 • Bldg 901 • Bldg 762 • Bldg 792 • Bldg 762A • Bldg 792A	(biased/reals) 10 10 10 11 11 24 24	5 (int) 2 (ext) 5 (int) 2 (ext) 5 (int) 2 (ext) 2 (ext) 5 (int) 1 (ext) 8 (int) 7 (int) 4 (ext)	None none none ACM ACM (762 inference) None none	40 CFR 763.86 5 CCR 1001-10 EPA 600/R-93/116 ("none" is <1% by volume)
Beryllium (swipes) • Bldg 550 • Bldg 761 • Bldg 901 • Bldg 762 • Bldg 792 • Bldg 762A • Bldg 792A	14 (total, biased, reals) 2 2 2 2 2 2 2	14 reals, 2 blanks 2 2 2 2 2 2 2	No contamination at any location	RIN 01D0630 OSHA ID-125G No results above action level (0.2µg/100cm <sup>2</sup> ) or investigative level (0.1 µg/100cm <sup>2</sup> ).
Radiological • Survey Unit: SEC-A-001  • Survey Unit: SEC-A-002  • Survey Unit: SEC-B-003	60 TSA & Smears (random + biased) 3 QC TSA 10% Scan  45 TSA & Smears (random + biased) 3 QC TSA 10% Scan  105 TSA & Smears (random + biased) 6 QC TSA 10% Scan	60 TSA & Smears (random + biased) 3 QC TSA 10% Scan  45 TSA & Smears (random + biased) 3 QC TSA 10% Scan  105 TSA & Smears (random + biased) 6 QC TSA 10% Scan	No contamination at any location above the action levels	No results above DCGL <sub>w</sub> or DCGL <sub>EMC</sub> action level (20 dpm/100cm <sup>2</sup> removable, 100 dpm/100cm <sup>2</sup> average, and 300 dpm/100cm <sup>2</sup> maximum.

<sup>A</sup> # of samples required is estimate only, based on miscellaneous material types; final # of samples at discretion of IH

<sup>B</sup> int – building interior, ext – building exterior

- beryllium

Consistent with similar PDS reports at the RFETS, verification confirms the following:

- Chain-of-Custody was intact from initial sampling through transport and final analysis;
- Preservation and hold-times were within tolerance; and
- Format and content of the data are clearly presented relative to goals of the project (i.e., to determine, with at least 95% confidence, that the survey units of interest are adequate for unrestricted radiological release, and no chemical hazards, or contamination, exist).

Verification of the PDS data also addresses quality records representing implementation of the following quality controls:

- Instrument calibrations, for accuracy;
- Laboratory control samples, for accuracy;
- Blanks, for accuracy;
- Duplicate measurements (surveys), for precision;
- Minimum Detectable Activity (MDA), Minimum Detection Limits (MDLs);
- Sample Analysis and Preparation methods.
- Count times, for sensitivity; and
- Sample preparations, for accuracy and representativeness.

All radiological data are organized into Survey Packages, which correlate to unique (MARSSIM) Survey Units. Each Survey Package is systematically reviewed by the responsible Radiological Engineer, a peer reviewer, and finally, Radiological Engineering Management. Chemical data are organized by sample number and corresponding sample location.

All relevant Quality records are managed in the Project File, and will be submitted to the CERCLA Administrative Record for permanent storage within 30 days of the approval of this RLC by the regulators.

## VALIDATION OF RESULTS

Validation consists of a technical review of all data that directly support the PDS decisions, so that any limitations of the data relative to project goals are delineated, and the associated data are qualified accordingly. Data were validated relative to the following:

- The DQOs as defined in the *Pre-Demolition Survey Plan for D&D Facilities* (K-H, 2/4/2001; i.e., did the final data achieve the initial DQOs of the project, particularly with respect to decisions), and

- Quality Assurance criteria (consistent with the various applicable sections in the MARSSIM, expressed in terms of the PARCCS parameters given in the subsections below).

MARSSIM criteria for the broad topic of "data quality assessment" used in final status surveys generally falls within the generic categories of quality assurance, quality control, data validation, and data assessment (including verification and validation). Table G-2 provides a "crosswalk" that lists the primary MARSSIM sections and generic data quality criteria (at top) and their corresponding implementation via the RLCR and project files.

All of the significant MARSSIM criteria listed in Table G-2 are summarily addressed within the "PARCC Parameters" discussion presented below. PARCCS parameters are congruent with "data descriptors" in the MARSSIM parlance and address characteristics of the data that must be defined for scientific integrity and defensibility. Recall that at least one "X" in each column of the table constitutes achievement of the MARSSIM quality objective (vs. one "X" in each row). The following discussion of the PARCC parameters -- Precision, Accuracy, Representativeness, Comparability, and Completeness, also include discussion of bias and sensitivity, two more data descriptors emphasized in MARSSIM.

## DQO DECISIONS

DQO decisions are summarized in Table G-1.

## PARCCS PARAMETERS

### Precision

#### *Radiological Surveys*

Duplicate measurements were acquired at the required frequency ( $\geq 5\%$  frequency of real surveys) on the MARSSIM survey grids. All duplicate measurements were within tolerance based on repeatability of results below the  $DCGL_w$ .

#### *Chemical Results*

Repeatability of beryllium results was not evaluated through field duplicates, based on the removable nature of the sampling process; this is consistent with radiological survey methodology, where repeatability is only evaluated relative to TSA measurements (fixed activity), and not removable activity. Overall repeatability within the sample set was evident based on all 14 sample results less than the detection limit ( $0.1 \mu\text{g}/100\text{cm}^2$ ).

Repeatability of asbestos results was not evaluated through field duplicates. Overall repeatability within the sample set was evident, however, based on all 40 samples results at less than detectable amounts ( $<1\%$  asbestos by volume).

Security Cluster

Inventory of Report & Project File	Executive Summary	Sec 1: Introduction	Sections 3 & 4: Hazards	Sec 6 & Attach. G: Data Quality Assessment	Attachments (Survey, Results, Maps, Data)	Data Package	CHARACTERIZATION & SURVEY PACKAGES	Summary Package Cover Sheets	(MARSSIM) Pre-Survey Calculation Worksheets	Sampling & Survey Instructions	Total Surface/Activity Data Sheets	Removable Contamination Sheets	Instrument Data Sheets	Survey Signatures	Grid Survey Maps	(MARSSIM) Post-Survey Verification Worksheets	Lab Results	Chain-of-Custody	Survey Unit Data Summary	QA/QC	Calibrations & Reference (Source) Standards	Sensitivity (MDC) determinations	Periodic Performance Checks
MARSSIM sec 4.9	X					X	X																
APP	X																						
SOPs	X																						
Training & Quals (personnel)	X																						
calibrations	X																						
QC Samples	X																						
sample quantities (adequacy of)	X																						
MARSSIM sec 5.2	X																						
Review - DOOS & Sampling Design	X																						
Review - DOOS & Sampling Design	X																						
Review - data review	X																						
graphical data review	X																						
conclusions	X																						
MARSSIM sec 9.0	X																						
Reports (no decision makers)	X																						
site description	X																						
analytical methods	X																						
background methods & MDA/MDC	X																						
measurement radiation	X																						
Chain-of-Custody	X																						
SOPs	X																						
Quality records	X																						
results by geographic location	X																						
defined level of data review	X																						
data quality indicators (PATCCS)	X																						
QC measurements	X																						
MARSSIM Appch E (DOA)	X																						
draw conclusions	X																						
review DOOS & survey design	X																						
MARSSIM Appch N	X																						
raw data, original data logs	X																						
QA assessments/CRC/CARs	X																						
data reduction/calculations	X																						
method validation	X																						
historical data	X																						

Table G-2. Security Cluster, Type 1 Facilities, PDS Compliance with MARSSIM Data Quality Guidelines.

MARSSIM Tabl-Security Cluster

## **Accuracy (and Bias)**

### ***Radiological Results (Surveys)***

Accuracy of radiological surveys is satisfactory based on RFETS-programmatic annual calibrations that establish instrument efficiencies and sensitivities for all instrumentation used on this project. Daily source checks also provided periodic checks to ensure that all sensors are within tolerance during daily operations. Calibration and calibration check results were within the RFETS and industry-standard requirement of  $\pm 20\%$  of the applicable reference standard values. Full-scale multi-point calibrations provide accuracies of  $\pm 10\%$  prior to implementation of survey instruments in the field, consistent with guidelines put forth in ANSI-N323.d

No biases were noted in the instrumentation, based on daily performance checks.

Distance measurements recorded on maps are within 3% of actual distances based on the laser technology used for distance measurements associated with the surveys.

### ***Chemical Results***

Accuracy for asbestos volumetric concentrations is based on the semi-quantitative technique of petrography via polarized light microscopy. Analysts can typically quantify components to within several percent at high concentrations ranging to  $\sim 1\%$  at low concentrations (i.e., presence or absence of the mineral of interest). Accuracy for the analysis is adequate, as the contrast between 0% and 1% is a clear distinction for the decision of "ACM" vs. "No ACM".

Accuracy of beryllium results was adequate based on acceptable percent recoveries of LCS performed on a laboratory batching basis.

Because no chemical results exceeded detection limits, evaluation of blank data was not required.

## **Representativeness**

Samples and surveys are representative based on the following criteria:

- Familiarity with facilities -- multiple walk-downs and collaborations by management and technical staff;
- Implementation of industry-standard Chain-of-Custody protocols;
- Compliance with sample preservation and hold times; and
- Documented and (site) approved methods, particularly RSPs for scans/surveys, and SOPs for asbestos sampling and beryllium swiping.
- *Chemical Characterization Package, Security Building Cluster Closure Project, Revision 1, Feb. 20, 2001*
- Radiological Survey Packages:
  - 01-0006, Survey Unit SEC-A-001

- 01-0007, Survey Unit SEC-A-002
- 01-0008, Survey Unit SEC-B-003

Surveys were also representative of the facilities based on a combination of random and biased measurement locations. Random survey measurements, 15 per Survey Unit, provided statistical confidence in radiological decisions, while biased locations provided additional confidence, as the locations were biased toward those areas with the greatest potential for radiological contamination (dust accumulation areas relative to airborne particulates, and high foot-traffic areas). All chemical sample locations are biased toward materials or locations with the highest potential for contamination.

No beta/gamma survey designs were implemented for the Security Cluster based on the conservatism of the transuranic limits used as DCGLs in the unrestricted release decision process. Stated differently, based on the well-established suite of actinides historically used at the RFETS, all of these actinides would emit alpha radiation in exceedance of the applicable transuranic DCGLs before other DCGLs would be exceeded for their respective Uranium species – the Building 371 Technical Position Paper, *Basis for Performing Solely Alpha Contamination Surveys for Building 371/374*, corroborates the use of this conservative approach.

Consistent with EPA's G-4 DQO process, the radiological survey design was optimized by checking actual measurement results (acquired during final status survey) against model output with original estimates. Use of actual sample/survey (result) variances in MARSSIM's DQO model confirms that an adequate number of samples/surveys were acquired

## **Completeness**

### ***Radiological Results***

All 3 Survey Packages were peer reviewed and approved by radiological engineering management. All radiological results are complete, valid without qualification, and form data sets with adequate quantities and quality of data for release decisions. Completeness of data for the project is summarized on table G-1.



### **Comparability**

All results presented are comparable with radiological survey and analytical data on a site- and DOE-complex wide basis. This comparability is based on:

- Use of standardized engineering units in the reporting of measurement results;
- Consistent sensitivities of measurements at  $\leq 50\%$  DCGL<sub>W</sub> ( $\leq 50\%$  DCGL<sub>EMC</sub> for scans);
- Use of site-approved procedures (RSPs, TBDs, and SOPs);
- Systematic quality controls; and
- Thorough documentation of the planning, sampling/analysis process, and data reduction into formats designed for making decisions posed from the project's original data quality objectives.

### **Sensitivity**

Adequate sensitivities, in units of dpm/100<sup>2</sup> cm, were attained for all surveys implemented based on MDAs at 50% of the transuranic DCGL<sub>W</sub> ( $\leq 50\%$  DCGL<sub>EMC</sub> for scans). Derivations of MDAs, for all instruments used, are given in each respective Radiological Survey Package. Nominal MDAs for each survey method are summarized as follows:

- Surveys (Eberline SAC-4) - removable contamination: 10 dpm/100cm<sup>2</sup>
- Surveys (NE Electra) - total surface contamination (TSA): 50 dpm/100cm<sup>2</sup>
- Surveys (NE Electra) – scans: <126 dpm/100 cm<sup>2</sup>

Sensitivities were adequate for all chemical analyses. Detection limits for beryllium were less than 0.1 ug/100cm<sup>2</sup>; asbestos was not detected at sensitivities to <<1% volume.

### **Summary**

In summary, the data presented in this report have been verified and validated relative to the project decisions as stated in the original DQOs. All media surveyed and sampled yielded results less than their associated action levels. Therefore, the Survey Units and buildings in question meet the unrestricted-release criteria with the confidences stated in this section and throughout the Security Cluster report.

# ATTACHMENT H

## Historical Site Assessment Reports


24

## **HISTORICAL FACILITY OVERVIEW FOR BUILDING 762A, PERSONNEL ACCESS CONTROL 707 (PACS 1)**

Building 762A, Personnel Access Control (PACS 1), was constructed in approximately 1989. It is located to the south of Building 762 and extends into the Building 707 parking lot. Building 762A was designed and constructed as an enhanced personnel control point to the protected area. The enhanced security consisted of, metal detectors, airport type X-Ray machine for hand carried items, and a badge and hand scanner to gain access to a turnstile to enter the protected area. After leaving the turnstile or entering it from the protected area personnel pass through a radiometric detector. The building has 3 X-ray machines, 7 metal detectors, 5 turnstiles, and 3 radiometric detectors. Building 762A is approximately 60' wide X 70' long X 17' high. Building 762A accounts for approximately 4200 square feet of floor space. The building has a 6" poured concrete floor. Bolted to the floor is a pre-engineered steel structure with a metal panel roof that slopes to the east and west for drainage. The building's outer walls consist of gypsum sheathing over insulation bating between metal studs covered with insulating board. The exterior insulation board was then covered with a trowled on stucco finish. The buildings interior walls are gypsum board over the batting insulation and have been painted. The Building 762A operators' work station has been hardened with a steel plate placed over the drywall and the windows in two sides of the room are bullet proof glass. Building 762A has emergency power to it and an UPS system for critical equipment in case of emergency power failure. Building 762A has a Men's/Women's Restroom. All the partition walls used 2" X 4" metal studs to support the drywall. Lead-based paints and asbestos may have been used during the construction of this facility. Building 762A has a drop acoustical tile ceiling. The building has its' own emergency generator. HVAC is supplied by an electric heat pump.

There is no information to indicate that PCB containing equipment was ever installed or stored in Building 762A. No known chemical or radioactive materials were ever stored in Building 762A. A WSRIC, either current or deleted, could not be found for Building 762A. Known or historical information does not indicate Building 762A was ever a RCRA storage or RCRA 90-day accumulation area. Building 762A was not constructed on any known IHSS/PAC land or soils.

Building 762A was always used as PACS 1. The facility currently is operational.



## **HISTORICAL FACILITY OVERVIEW FOR BUILDING 762, GUARD POST, PORTAL 1**


Building 762 Guard Post, Portal 1, was constructed in approximately 1983. Building 762 was designed and constructed as a Guard Post and vehicular access control point to the protected area. It is located at the southwest corner of Ninth Street and the Patrol Road in the protected area. The Guard Post allowed access to the protected area when security was enhanced for the plutonium buildings by the construction of the security zone. Building 762 is approximately 16' wide X 23' long X 11' 6" high. Building 762 accounts for approximately 368 square feet of floor space. The building has a 4" poured concrete floor and twin-tee prestressed concrete roof/deck which is sloped to the west for roof drainage and the roof has a 4' overhang on all four sides. The roof covering construction is 2" lightweight concrete over the twin-tee, Styrofoam insulation, felt, asphalt and gravel. The building's outer walls are 6" thick poured steel reinforced concrete construction. Building 762 Guard Post was designed with all bullet proof glass, gun or weapon, slots in all four outer walls, and a double steel plate access door with bullet proof glass. Building 762 has a Men's/Women's Restroom. Building 762 has emergency power to it and an UPS system for critical equipment in case of emergency power failure. The interior walls of Building 762 have been insulated, covered with drywall, and painted. All the partition walls used 2" X 4" metal studs to support the drywall. Lead-based paints and asbestos may have been used during the construction of this facility. Building 762 has a drop acoustical tile ceiling that has been insulated. Radiometric detection equipment is located in the personnel walkway and the vehicular access driveway that is controlled from Building 762.

There is no information to indicate that PCB containing equipment was ever installed or stored in Building 762. No known chemical or radioactive materials were ever stored in Building 762. A WSRIC, either current or deleted, could not be found for Building 762. Known or historical information does not indicate Building 762 was ever a RCRA storage or RCRA 90-day accumulation area. Building 762 was not constructed on any known IHSS/PAC land or soils.

Building 762 was always used as a Guard Post, Portal 1. The facility currently is operational.



file://A:\Building 762, Security Cluster, Guard Post Portal 1, Looking North.jpg




## **HISTORICAL FACILITY OVERVIEW FOR BUILDING 792, GUARD POST, PORTAL 3**

Building 792 Guard Post, Portal 3, was constructed in approximately 1983. Building 792 was designed and constructed as a Guard Post and personnel control point to the protected area. It is located at the southwest corner of the personnel walkway from Building 792A and the Patrol Road in the protected area. The Guard Post allowed access to the protected area when security was enhanced for the plutonium buildings by the construction of the security zone. Building 792 is approximately 16' wide X 18' long X 11' 6" high. Building 792 accounts for approximately 288 square feet of floor space. The building has a 4" poured concrete floor and twin-tee prestressed concrete roof/deck which is sloped to the west for roof drainage and the roof has a 4' overhang on all four sides. The roof covering construction is 2" lightweight concrete over the twin-tee, Styrofoam insulation, felt, asphalt and gravel. The building's outer walls are 6" thick poured steel reinforced concrete construction. Building 792 Guard Post was designed with all bullet proof glass, gun or weapon, slots in all four outer walls, and a double steel plate access door with bullet proof glass. Building 792 has a Men's/Women's Restroom. Building 792 has emergency power to it and an UPS system for critical equipment in case of emergency power failure. The interior walls of Building 792 have been insulated, covered with drywall, and painted. All the partition walls used 2" X 4" metal studs to support the drywall. Lead-based paints and asbestos may have been used during the construction of this facility. Building 792 has a drop acoustical tile ceiling that has been insulated. Radiometric detection equipment is located in the personnel walkway that is controlled from Building 792.

There is no information to indicate that PCB containing equipment was ever installed or stored in Building 792. No known chemical or radioactive materials were ever stored in Building 792. A WSRIC, either current or deleted, could not be found for Building 792. Known or historical information does not indicate Building 792 was ever a RCRA storage or RCRA 90-day accumulation area. Building 792 was not constructed on any known IHSS/PAC land or soils.

Building 792 was always used as a Guard Post, Portal 1. The facility currently is operational.





82

file://A:\Building 792, Security Cluster, Guard Post Portal 3, Looking South.jpg


1/25/01

## **HISTORICAL FACILITY OVERVIEW FOR BUILDING 550, GUARD TOWER NUMBER 3**

Building 550, Guard Tower Number 3, was constructed in approximately 1983 as part of the enhanced security zone surrounding the plutonium buildings. Building 550 was designed and constructed as a Guard Tower to provide an elevated line of sight and firing platform for the fenced portion of the zone from Building 792 to the top of the hill southwest of Building 371. Building 550 is approximately 12' square X 35' high. Building 550 accounts for approximately 144 square feet of floor space. The building has a 4" thick reinforced concrete floor first floor. The building's outer walls are 8" thick reinforced concrete block construction with the void space filled with grout. The walls reinforced concrete foundation is tied into a 15' square, 14 inch thick reinforced concrete block 3' below grade. An open metal grating stair leads up to the equipment room level at 16' above the ground floor. The floor at this level is an 8" thick reinforced concrete slab. The walls at this level are the same construction as below this level and are approximately 10' high to the next level. This level is the observation deck. Its' floor is a 8" thick reinforced concrete slab that supports 8"thick reinforced concrete walls to the bottom of the windows. Building 550 was designed with all bullet proof glass, gun or weapon, slots in all four outer walls. The roof of the tower is supported on all four corners with square metal structural tubing. It is a 7" thick reinforced concrete slab 15' square that slopes away from the side where the building entrance is. The roof is covered with rigid insulation and topped with EDPM membrane. A searchlight is mounted on the roof and operated from the observation deck. The tower has emergency power to it and an UPS system for critical equipment in case of emergency power failure. The interior walls of observation deck have been insulated, covered with drywall, and painted. Lead-based paints and asbestos may have been used during the construction of this facility.

There is no information to indicate that PCB containing equipment was ever installed or stored in Building 550. No known chemical or radioactive materials were ever stored in Building 550. A WSRIC, either current or deleted, could not be found for Building 550. Known or historical information does not indicate Building 550 was ever a RCRA storage or RCRA 90-day accumulation area. Building 550 was not constructed on any known IHSS/PAC land or soils.

Building 550 was always used as a Guard Tower. The facility currently is not operational.




## **HISTORICAL FACILITY OVERVIEW FOR BUILDING 761, GUARD TOWER NUMBER 1**

Building 761, Guard Tower Number 1, was constructed in approximately 1983 as part of the enhanced security zone surrounding the plutonium buildings. Building 761 was designed and constructed as a Guard Tower to provide an elevated line of sight and firing platform for the fenced portion of the zone from Building 762 to the top of the hill above Building 995. Building 761 is approximately 12' square X 45" high. Building 761 accounts for approximately 144 square feet of floor space. The building has a 4" thick reinforced concrete floor first floor. The building's outer walls are 8" thick reinforced concrete block construction with the void space filled with grout. The walls reinforced concrete foundation is tied into a 15' square, 14 inch thick reinforced concrete block 3' below grade. An open metal grating stair leads up to the equipment room level at 26' above the ground floor. The floor at this level is an 8" thick reinforced concrete slab. The walls at this level are the same construction as below this level and are approximately 10' high to the next level. This level is the observation deck. Its' floor is a 8" thick reinforced concrete slab that supports 8"thick reinforced concrete walls to the bottom of the windows. Building 761 was designed with all bullet proof glass, gun or weapon, slots in all four outer walls. The roof of the tower is supported on all four corners with square metal structural tubing. It is a 7" thick reinforced concrete slab 15' square that slopes away from the side where the building entrance is. The roof is covered with rigid insulation and topped with EDPM membrane. A searchlight is mounted on the roof and operated from the observation deck. The tower has emergency power to it and an UPS system for critical equipment in case of emergency power failure. The interior walls of observation deck have been insulated, covered with drywall, and painted. Lead-based paints and asbestos may have been used during the construction of this facility.

There is no information to indicate that PCB containing equipment was ever installed or stored in Building 761. No known chemical or radioactive materials were ever stored in Building 761. A WSRIC, either current or deleted, could not be found for Building 761. Known or historical information does not indicate Building 761 was ever a RCRA storage or RCRA 90-day accumulation area. Building 761 was not constructed on any known IHSS/PAC land or soils.

Building 761 was always used as a Guard Tower. The facility currently is not operational.




85

## **HISTORICAL FACILITY OVERVIEW FOR BUILDING 901, GUARD TOWER NUMBER 2**

Building 901, Guard Tower Number 2, was constructed in approximately 1983 as part of the enhanced security zone surrounding the plutonium buildings. Building 901 was designed and constructed as a Guard Tower to provide an elevated line of sight and firing platform for the fenced portion of the zone from Building 792 to the top of the hill above Building 995. Building 901 is approximately 12' square X 45" high. Building 901 accounts for approximately 144 square feet of floor space. The building has a 4" thick reinforced concrete floor first floor. The building's outer walls are 8" thick reinforced concrete block construction with the void space filled with grout. The walls reinforced concrete foundation is tied into a 15' square, 14 inch thick reinforced concrete block 3' below grade. An open metal grating stair leads up to the equipment room level at 26' above the ground floor. The floor at this level is an 8" thick reinforced concrete slab. The walls at this level are the same construction as below this level and are approximately 10' high to the next level. This level is the observation deck. Its' floor is a 8" thick reinforced concrete slab that supports 8"thick reinforced concrete walls to the bottom of the windows. Building 901 was designed with all bullet proof glass, gun or weapon, slots in all four outer walls. The roof of the tower is supported on all four corners with square metal structural tubing. It is a 7" thick reinforced concrete slab 15' square that slopes away from the side where the building entrance is. The roof is covered with rigid insulation and topped with EDPM membrane. A searchlight is mounted on the roof and operated from the observation deck. The tower has emergency power to it and an UPS system for critical equipment in case of emergency power failure. The interior walls of observation deck have been insulated, covered with drywall, and painted. Lead-based paints and asbestos may have been used during the construction of this facility.

There is no information to indicate that PCB containing equipment was ever installed or stored in Building 901. No known chemical or radioactive materials were ever stored in Building 901. A WSRIC, either current or deleted, could not be found for Building 901. Known or historical information does not indicate Building 901 was ever a RCRA storage or RCRA 90-day accumulation area. Building 901 was not constructed on any known IHSS/PAC land or soils.

Building 901 was always used as a Guard Tower. The facility currently is not operational.



**D&D RISS Facility Characterization  
Historical Site Assessment - Interview Checklist**

**Facility ID: Building 762A, PAC 1**

**Facility Type (1, 2, or 3): Type 1**

This facility specific Historical Site Assessment (HSA) - Interview Checklist has been conducted in accordance with:  
*D&D Characterization Protocol*, RFETS MAN-077-DDCP, latest version, and  
*Facility Disposition Program Manual*, RFETS MAN-076-FDPM, latest version

**Personnel Interviewed (Name, Title, and Function)** Lou C. Richmond, Team Lead Operation Service WSL.L.C. X8361  
P-212-6598, T-119, Room 54.

**What time frame did the interviewee work in the facility?** Since 1970 as a SPO, Lieutenant, Captain, and at his current position as Team Lead Operation Service.

**Has the building configuration changed since you worked in the building?** Yes If so, in what way? A hand scanner was added to the badge reader in order to gain access to the turnstiles to the protected zone

**What types of equipment were in the building during the interviewee's time in the facility?** X-ray equipment for hand carried items, metal detectors, badge readers, hand scanners, turnstiles, computer equipment, and communication equipment.

**Where was the equipment located?** (specific rooms/areas) In the entry area and the computer room

**Were any radioactive materials or equipment handled in the building?** If so, what types and where? No known radioactive material were handled or stored in the building.

**Were any chemicals (e.g., Asbestos, Beryllium, Lead, RCRA/CERCLA Constituents, PCBs, etc.) handled in the building?** If so, what types and where? No known chemicals or RCRA/CERCLA constituents were handled in the building. Historical Release Report (HRR) information does not identify the building as being on or near IHSS/PAC land or soils.

**Did any spills or uncontrolled release of radioactive materials or chemicals occur while you worked in the building?** If so, what types and where? N/A. No known radioactive or chemical spills or uncontrolled releases occurred in the building.

**Were these spills/releases cleaned up?** If so, how were cleaned up? N/A. no spills/releases occurred in the building.

**Do you know of any additional issues, concerns, or process knowledge that could affect facility characterization?** No none.

Prepared By:

Dean Burton

Print Name

Signature

Date



## D&D RISS Facility Characterization Historical Site Assessment - Interview Checklist

**Facility ID: Building 762, Portal 1**

**Facility Type (1, 2, or 3): Type 1**

This facility specific Historical Site Assessment (HSA) - Interview Checklist has been conducted in accordance with:  
*D&D Characterization Protocol*, RFETS MAN-077-DDCP, latest version, and  
*Facility Disposition Program Manual*, RFETS MAN-076-FDPM, latest version

Personnel Interviewed (Name, Title, and Function) Lou C. Richmond, Team Lead Operation Service WSL.L.C. X8361  
P-212-6598, T-119, Room 54.

What time frame did the interviewee work in the facility? Since 1970 as a SPO, Lieutenant, Captain, and at his current position as Team Lead Operation Service.

Has the building configuration changed since you worked in the building? If so, in what way? There were no changes made in the building configuration.

What types of equipment were in the building during the interviewee's time in the facility? Radiometric detection equipment and communication to keep in contact with other Security Force Officers and buildings.

Where was the equipment located? (specific rooms/areas) Radiometric detection detectors are located in the walk way into the protected zone and electronic equipment for the detectors and communication inside the building.

Were any radioactive materials or equipment handled in the building? If so, what types and where? No known radioactive material were handled or stored in the building.

Were any chemicals (e.g., Asbestos, Beryllium, Lead, RCRA/CERCLA Constituents, PCBs, etc.) handled in the building? If so, what types and where? No known chemicals or RCRA/CERCLA constituents were handled in the building. Historical Release Report (HRR) information does not identify the building as being on or near IHSS/PAC land or soils.

Did any spills or uncontrolled release of radioactive materials or chemicals occur while you worked in the building? If so, what types and where? N/A. No known radioactive or chemical spills or uncontrolled releases occurred in the building.

Were these spills/releases cleaned up? If so, how were cleaned up? N/A. no spills/releases occurred in the building.

Do you know of any additional issues, concerns, or process knowledge that could affect facility characterization? No none.

Prepared By:

Dean Burton

Print Name

Signature

Date

## D&D RISS Facility Characterization Historical Site Assessment - Interview Checklist

**Facility ID: Building 792A, PAC 3**

**Facility Type (1, 2, or 3): Type 1**

This facility specific Historical Site Assessment (HSA) - Interview Checklist has been conducted in accordance with:  
*D&D Characterization Protocol*, RFETS MAN-077-DDCP, latest version, and  
*Facility Disposition Program Manual*, RFETS MAN-076-FDPM, latest version

Personnel Interviewed (Name, Title, and Function) Lou C. Richmond, Team Lead Operation Service WSL.L.C. X8361 P-212-6598, T-119, Room 54.

What time frame did the interviewee work in the facility? Since 1970 as a SPO, Lieutenant, Captain, and at his current position as Team Lead Operation Service.

Has the building configuration changed since you worked in the building? Yes If so, in what way? A hand scanner was added to the badge reader in order to gain access to the turnstiles to the protected zone

What types of equipment were in the building during the interviewee's time in the facility? X-ray equipment for hand carried items, metal detector, badge readers, hand scanners, turnstiles, computer equipment, and communication equipment.

Where was the equipment located? (specific rooms/areas) In the entry area and the computer room

Were any radioactive materials or equipment handled in the building? If so, what types and where? No known radioactive material were handled or stored in the building.

Were any chemicals (e.g., Asbestos, Beryllium, Lead, RCRA/CERCLA Constituents, PCBs, etc.) handled in the building? If so, what types and where? No known chemicals or RCRA/CERCLA constituents were handled in the building. Historical Release Report (HRR) information does not identify the building as being on or near IHSS/PAC land or soils.

Did any spills or uncontrolled release of radioactive materials or chemicals occur while you worked in the building? If so, what types and where? N/A. No known radioactive or chemical spills or uncontrolled releases occurred in the building.

Were these spills/releases cleaned up? If so, how were cleaned up? N/A. no spills/releases occurred in the building.

Do you know of any additional issues, concerns, or process knowledge that could affect facility characterization? No none.

Prepared By:

Dean Burton

Print Name

Signature

Date

## D&D RISS Facility Characterization Historical Site Assessment - Interview Checklist

**Facility ID:** Building 792, Portal 3

**Facility Type (1, 2, or 3):** Type 1

This facility specific Historical Site Assessment (HSA) - Interview Checklist has been conducted in accordance with:  
*D&D Characterization Protocol*, RFETS MAN-077-DDCP, latest version, and  
*Facility Disposition Program Manual*, RFETS MAN-076-FDPM, latest version

**Personnel Interviewed (Name, Title, and Function)** Lou C. Richmond, Team Lead Operation Service WSL.L.C. X8361 P-212-6598, T-119, Room 54.

**What time frame did the interviewee work in the facility?** Since 1970 as a SPO, Lieutenant, Captain, and at his current position as Team Lead Operation Service.

**Has the building configuration changed since you worked in the building? If so, in what way?** There were no changes made in the building configuration.

**What types of equipment were in the building during the interviewee's time in the facility?** Radiometric detection equipment and communication to keep in contact with other Security Force Officers and buildings.

**Where was the equipment located? (specific rooms/areas)** Radiometric detection detectors are located in the walk way into the protected zone and electronic equipment for the detectors and communication equipment is inside the building.

**Were any radioactive materials or equipment handled in the building? If so, what types and where?** No known radioactive material were handled or stored in the building.

**Were any chemicals (e.g., Asbestos, Beryllium, Lead, RCRA/CERCLA Constituents, PCBs, etc.) handled in the building? If so, what types and where?** No known chemicals or RCRA/CERCLA constituents were handled in the building. Historical Release Report (HRR) information does not identify the building as being on or near IHSS/PAC land or soils.

**Did any spills or uncontrolled release of radioactive materials or chemicals occur while you worked in the building? If so, what types and where?** N/A. No known radioactive or chemical spills or uncontrolled releases occurred in the building.

**Were these spills/releases cleaned up? If so, how were cleaned up?** N/A. no spills/releases occurred in the building.

**Do you know of any additional issues, concerns, or process knowledge that could affect facility characterization?** No none.

Prepared By:

Dean Burton

Print Name

*Dean Burton*

Signature

1 03/05/01

Date

## D&D RISS Facility Characterization Historical Site Assessment - Interview Checklist

**Facility ID:** Building 550, Guard Tower 3

**Facility Type (1, 2, or 3):** Type 1

This facility specific Historical Site Assessment (HSA) - Interview Checklist has been conducted in accordance with:  
*D&D Characterization Protocol*, RFETS MAN-077-DDCP, latest version, and  
*Facility Disposition Program Manual*, RFETS MAN-076-FDPM, latest version

**Personnel Interviewed (Name, Title, and Function)** Lou C. Richmond, Team Lead Operation Service WSL.L.C. X8361 P-212-6598, T-119, Room 54.

**What time frame did the interviewee work in the facility?** Since 1970 as a SPO, Lieutenant, Captain, and at his current position as Team Lead Operation Service.

**Has the building configuration changed since you worked in the building? If so, in what way?** There were no changes in the building.

**What types of equipment were in the building during the interviewee's time in the facility?** Electronic equipment for monitoring the Security Zone in its' area of control. Communication equipment to keep in contact with other Security Forces Officers and buildings

**Where was the equipment located? (specific rooms/areas)** On the equipment level and the observation level of the building.

**Were any radioactive materials or equipment handled in the building? If so, what types and where?** No known radioactive material were handled or stored in the building.

**Were any chemicals (e.g., Asbestos, Beryllium, Lead, RCRA/CERCLA Constituents, PCBs, etc.) handled in the building? If so, what types and where?** No known chemicals or RCRA/CERCLA constituents were handled in the building. Historical Release Report (HRR) information does not identify the building as being on or near IHSS/PAC land or soils.

**Did any spills or uncontrolled release of radioactive materials or chemicals occur while you worked in the building? If so, what types and where?** N/A. No known radioactive or chemical spills or uncontrolled releases occurred in the building.

**Were these spills/releases cleaned up? If so, how were cleaned up?** N/A. no spills/releases occurred in the building.

**Do you know of any additional issues, concerns, or process knowledge that could affect facility characterization?** No none.

Prepared By:

Dean Burton

Print Name

Signature

Date

92

## D&D RISS Facility Characterization Historical Site Assessment - Interview Checklist

**Facility ID: Building 761, Guard Tower 1**

**Facility Type (1, 2, or 3): Type 1**

This facility specific Historical Site Assessment (HSA) - Interview Checklist has been conducted in accordance with:  
*D&D Characterization Protocol*, RFETS MAN-077-DDCP, latest version, and  
*Facility Disposition Program Manual*, RFETS MAN-076-FDPM, latest version

Personnel Interviewed (Name, Title, and Function) Lou C. Richmond, Team Lead Operation Service WSL.L.C. X8361 P-212-6598, T-119, Room 54.

What time frame did the interviewee work in the facility? Since 1970 as a SPO, Lieutenant, Captain, and at his current position as Team Lead Operation Service.

Has the building configuration changed since you worked in the building? If so, in what way? There were no changes in the building.

What types of equipment were in the building during the interviewee's time in the facility? Electronic equipment for monitoring the Security Zone in its' area of control. Communication equipment to keep in contact with other Security Forces Officers and buildings

Where was the equipment located? (specific rooms/areas) On the equipment level and the observation level of the building.

Were any radioactive materials or equipment handled in the building? If so, what types and where? No known radioactive material were handled or stored in the building.

Were any chemicals (e.g., Asbestos, Beryllium, Lead, RCRA/CERCLA Constituents, PCBs, etc.) handled in the building? If so, what types and where? No known chemicals or RCRA/CERCLA constituents were handled in the building. Historical Release Report (HRR) information does not identify the building as being on or near IHSS/PAC land or soils.

Did any spills or uncontrolled release of radioactive materials or chemicals occur while you worked in the building? If so, what types and where? N/A. No known radioactive or chemical spills or uncontrolled releases occurred in the building.

Were these spills/releases cleaned up? If so, how were cleaned up? N/A. no spills/releases occurred in the building.

Do you know of any additional issues, concerns, or process knowledge that could affect facility characterization? No none.

Prepared By:

Dean Burton  
Print Name

Signature

Date

## D&D RISS Facility Characterization Historical Site Assessment - Interview Checklist

**Facility ID: Building 901, Guard Tower 2**

**Facility Type (1, 2, or 3): Type 1**

This facility specific Historical Site Assessment (HSA) - Interview Checklist has been conducted in accordance with:

*D&D Characterization Protocol*, RFETS MAN-077-DDCP, latest version, and

*Facility Disposition Program Manual*, RFETS MAN-076-FDPM, latest version

**Personnel Interviewed (Name, Title, and Function)** Lou C. Richmond, Team Lead Operation Service WSL.L.C. X8361 P-212-6598, T-119, Room 54.

**What time frame did the interviewee work in the facility?** Since 1970 as a SPO, Lieutenant, Captain, and at his current position as Team Lead Operation Service.

**Has the building configuration changed since you worked in the building? If so, in what way?** There were no changes in the building.

**What types of equipment were in the building during the interviewee's time in the facility?** Electronic equipment for monitoring the Security Zone in its' area of control. Communication equipment to keep in contact with other Security Forces Officers and buildings

**Where was the equipment located? (specific rooms/areas)** On the equipment level and the observation level of the building.

**Were any radioactive materials or equipment handled in the building? If so, what types and where?** No known radioactive material were handled or stored in the building.

**Were any chemicals (e.g., Asbestos, Beryllium, Lead, RCRA/CERCLA Constituents, PCBs, etc.) handled in the building? If so, what types and where?** No known chemicals or RCRA/CERCLA constituents were handled in the building. Historical Release Report (HRR) information does not identify the building as being on or near IHSS/PAC land or soils.

**Did any spills or uncontrolled release of radioactive materials or chemicals occur while you worked in the building? If so, what types and where?** N/A. No known radioactive or chemical spills or uncontrolled releases occurred in the building.

**Were these spills/releases cleaned up? If so, how were cleaned up?** N/A. no spills/releases occurred in the building.

**Do you know of any additional issues, concerns, or process knowledge that could affect facility characterization?** No none.

Prepared By:

Dean Burton

Print Name

Signature

Date

94

# D&D RISS Facility Characterization Historical Site Assessment Report

Waste Volume Estimates and Material Types For Building 762A PAC 1						
Concrete (cu ft)	Wood (cu ft)	Metal (cu ft)	Corrugated Sheet Metal (cu ft)	Wall Board (cu ft)	ACM	Other Waste
6929	None	1500	None	410	TBD	Glass 15 cu ft, ridge insulation 1211 cu ft acoustical tile 203 cu ft fiber glass insulation 1687 cu ft raised floor panels 52 cu ft

**Prepared By:**

Dean Burton

Print Name \_\_\_\_\_

**Signature**

Date \_\_\_\_\_

**Reviewed By:**

Gerard Kelly

Print Name \_\_\_\_\_

Signature \_\_\_\_\_

Date \_\_\_\_\_

# D&D RISS Facility Characterization Historical Site Assessment Report

Waste Volume Estimates and Material Types For Building 792 Portal 3						
Concrete (cu ft)	Wood (cu ft)	Metal (cu ft)	Corrugated Sheet Metal (cu ft)	Wall Board (cu ft)	ACM	Other Waste
896	None	5	None	44	TBD	Glass 20 cu ft, insulation 272 cu ft acoustical tile 20 cu ft

Prepared By: Dean Burton / Dean Burton / 3/5/01  
 Print Name Signature Date

Reviewed By: Gerard Kelly / *Gerard Kelly* / 3/5/01  
Print Name Signature Date

44



# D&D RISS Facility Characterization Historical Site Assessment Report

Waste Volume Estimates and Material Types For Building 762 Portal 1						
Concrete (cu ft)	Wood (cu ft)	Metal (cu ft)	Corrugated Sheet Metal (cu ft)	Wall Board (cu ft)	ACM	Other Waste
1069	None	5	None	50	TBD	Glass 20 cu ft, insulation 311 cu ft acoustical tile 24 cu ft

**Prepared By:**

Dean Burton

Print Name \_\_\_\_\_

**Signature**

Date \_\_\_\_\_

Reviewed By:

Gerard Kelly

Print Name \_\_\_\_\_

**Signature**

Date \_\_\_\_\_

# D&D RISS Facility Characterization Historical Site Assessment Report

Waste Volume Estimates and Material Types For Building 792A PAC 3						
Concrete (cu ft)	Wood (cu ft)	Metal (cu ft)	Corrugated Sheet Metal (cu ft)	Wall Board (cu ft)	ACM	Other Waste
3118	None	675	None	185	TBD	Glass 7 cu ft, ridge insulation 545 cu ft acoustical tile 91 cu ft fiber glass insulation 759 cu ft

**Prepared By:**

Dean Burton

Print Name \_\_\_\_\_

**Signature**

Date \_\_\_\_\_

Reviewed By:

Gerard Kelly

Print Name \_\_\_\_\_

Signature \_\_\_\_\_

Date \_\_\_\_\_

# Historical Site Assessment Report

Glass 67 cu ft,  
insulation 75  
cu ft

Date \_\_\_\_\_

Date

# D&D RISS Facility Characterization Historical Site Assessment Report

Waste Volume Estimates and Material Types For Building 761 Guard Tower 1						
Concrete (cu ft)	Wood (cu ft)	Metal (cu ft)	Corrugated Sheet Metal (cu ft)	Wall Board (cu ft)	ACM	Other Waste
2121	None	100	None	4	TBD	Glass 67 cu ft, insulation 75 cu ft

**Prepared By:**

**Dean Burton**

Print Name

**Signature**

Date

**Reviewed By:**

Gerard Kelly

Print Name \_\_\_\_\_

Signature

Date \_\_\_\_\_

# D&D RISS Facility Characterization Historical Site Assessment Report

Waste Volume Estimates and Material Types For Building 901 Guard Tower 2						
Concrete (cu ft)	Wood (cu ft)	Metal (cu ft)	Corrugated Sheet Metal (cu ft)	Wall Board (cu ft)	ACM	Other Waste
2121	None	100	None	4	TBD	Glass 67 cu ft, insulation 75 cu ft

Prepared By:

Dean Burton

Print Name

Signature

Date

Reviewed By:

Gerard Kelly

Print Name

Signature

Date

10/1/01